

Verification Report for

Project : SBPIL Waste Heat to Power Project, Borjhara, India.

UCR Project ID: 400

Name of Verifier	SQAC Certification Pvt. Ltd.
Date of Issue	March 12, 2024
Project Proponent	M/s Shri Bajrang Power and Ispat Limited (SBPIL)
UCR Project Aggregator	M/s Carbon Equalizers.
Work carried by	Ms. Sheetal Wader
Work reviewed by	Mr. Santosh Nair

Summary:

SQAC Certification Pvt. Ltd. has performed verification of the "SBPIL Waste Heat to Power Project, Borjhara, India". The project activity is the installation of waste heat recovery boilers (WHRBs) and turbine generators to generate electrical power from the waste heat gases produced during the manufacture of sponge iron. The project activity results in reduced carbon emissions by displacing equivalent amount of power generation in Chhattisgarh State Electricity Board (CSEB) grid.

The project activity meets the following UN SDG's:















Verification for the period: **01/09/2015 - 31/12/2022** (07 years 04 months)

The GHG emission reductions were calculated on the basis of UCR Protocols which draws reference from, UCR Protocol Standard Baseline, CDM UNFCCC Methodology, ACM0012 Waste energy recovery Version 6.0. The verification was done was done remotely by way of video calls / verification, phone calls and submission of documents for verification through emails.

SQAC is able to certify that the emission reductions from SBPIL Waste Heat to Power Project, Borjhara, India, (UCR ID – 400) for the period 01/09/2015 to 31/12/2022 amounts to 5,02,989 CoUs (5,02,989 tCO₂eq)

Accredited by 5 Jupiter House, Callera Park, Aldermaston, Reading Berkshire RG7 8NN, United Kingdom (UK).

India Office: Off. No. 4, Fifth Floor, Buildmore Business Park, New Canca Bypass Road, Khorlim, Mapusa, Goa – 403 507

Web: www.sqac.in

Email: info@sqac.in Tel: 7219716786 / 87





Detailed Verification Report:

Purpose:

The GOEL GROUP of Industries is a leading business conglomerate in Chhattisgarh, India. It operates a Re-Rolling Mill named M/s Shri Bajrang Alliance Ltd. (formerly M/s Shri Bajrang Alloys Ltd) in the Iron & Steel sector. Moreover, M/s Shri Bajrang Power & Ispat Ltd, a part of the group, produces TMT Bars sold under the brand Goel TMT.

The plant was commissioned in 2005 (also called Unit I) manufactures of TMT Bars, Ferro alloys, steel billets, sponge iron and fly ash bricks. The project activity takes place at a sponge iron plant (Unit I) and involves the generation of electrical power through the installation of waste heat recovery boilers and steam turbine generators (STGs).

The waste heat produced during the manufacture of sponge iron is passed through boilers and the resultant steam is utilised to generate electrical power. The power generated from two condensing turbines (8 MW and 10 MW) is consumed in captive requirements and surplus is exported to the grid via Chhattisgarh State Electricity Board (CSEB).

The energy generated in the project is measured by meters installed at both STGs in the power plant. The project activity was commissioned in phase wise wherein the 8 MW STG started operating on 12/07/2005 and 10 MW STG started operating on 31/08/2005 and has been operating till date on regular basis.

Related Documents	Date
Factory's License	15/07/2005
Electrical Inspector's Report of the Installations	16/06/2005
Permission for running 18 MW TG set captive power plant	2005
Copy of Purchase Order for Boiler placed on M/s Thermax Limited	19/04/2004
Copy of Purchase Order for Turbine placed on M/s Triveni	19/04/2004
Engineering Industries Ltd	
Boilers Inspection Report	01/06/2022 and
	16/08/2022


The project activity entails utilisation of waste heat of flue gases generated in Direct Reduced Iron (DRI) kilns of sponge iron plants of SBPIL (Project Proponent or PP hereafter) in power generation. DRI, is a type of kiln used in the production of sponge iron, where iron ore is reduced to sponge iron using coal & Iron ore through a rotary Kiln at high temperature (1000 °C).




The reduction process produces carbon dioxide and carbon monoxide. The waste heat from the flue gases is harnessed to generate steam in Waste Heat Recovery Boilers (WHRB), which is then utilized to power two turbines with a combined capacity of 18MW (8MW + 10MW). The 8MW turbine generator was connected to the grid on 12/07/2005, followed by the synchronization of the 10MW turbine generator on 31/08/2005. Subsequent to these synchronizations, the turbines underwent testing and trials on 01/09/2005, marking the earliest date when the project could start supplying electricity to the grid.















Location of project activity:

Urla Industrial Area

Village : Borjhara District : Raipur,

State : Chhattisgarh,

Country: India.

Latitude : 21º18'30.8" N (21.3085) Longitude : 81º35'6.8" E (81.5852)







Scope:

The scope covers verification of emission reductions from the project - SBPIL Waste Heat to Power Project, Borjhara, India, (UCR ID – 400).

Criteria:

Verification criteria is as per the requirements of UCR Standard.

Description of project:

In the project activity two turbo Generators (TG) having a combined capacity of 18 MW were linked with two WHRBs attached to each sponge iron kiln. Due to inadequate steam generation in WHRBs the full capacity of the WHR project as predicted could not be utilised. After the implementation of the AFBC boiler, the excess steam available from the same is being diverted to the WHR project to achieve full generation capacity of 18 MW turbine. Electricity generated from this diverted steam on account of the AFBC boiler is however not claimed as emission reductions (CoUs) in the current project activity.

The majority of sponge iron in India is manufactured through the direct reduction process. This process involves passing coal and iron ore through a rotary kiln at high temperatures (over 1000°C) to reduce the iron ore to sponge iron. The reduction process yields carbon dioxide and carbon monoxide. These gases leave the kiln at high temperature (950°C) and may be utilised to generate power. After leaving the kiln the hot gases are passed through an after-burner chamber where further oxidation of the gases occurs, i.e. carbon monoxide to carbon dioxide. The gases are then fed to waste heat recovery boilers and then drawn through electrostatic precipitators and ultimately released via the stack.

Sr. No	Turbine Details	Make	Date Commissioned
1.	8 MW condensing TG -1	Triveni, India	12/07/2005
2.	10 MW condensing TG-2	Triveni, India	31/08/2005

	Sr. No	Boiler Details	Make
Ī	1	2 x 38 TPH, 66 Kg/cm2, 490 ± 5° C	Thermax India

The project activity (also known as Unit I within the group of facilities operated and owned by the PP) comprises of two WHRBs, one compatible for 38TPH of steam generation installed at the tail end of second number 350TPD DRI Kiln and another WHRB of 38TPH capacity at the tail end of first number of 350 TPD Kiln along with one AFBC Boiler of 60 TPH steam generation capacity equipped with Water



Cooled Condenser.

Flue gases temp and pressure : 950°C, -1 to -5 mmWC (Inlet)

Steam generated pressure and temp : 66 ATA, 490 ± 5 °C

Heat that is extracted from the hot gas is utilized in the transforming water to high temperature to high pressure steam, to run conventional condensing type Steam Turbo Generator for generation of electricity as a part of forward and backward integration process.

United Nations Sustainable Development Goals:

The project activity displaces CSEB grid power, part of WR grid, which is predominantly fossil fuel based. In the absence of the project activity equivalent amount of power generation would have taken place through fossil fuel dominated power generating stations.

Positive contribution of the project to the following Sustainable Development Goals:

Development Goals	Targeted SDG	Target Indicator (SDG Indicator)
13 CLIMATE ACTION	13.2: Integrate climate change measures into national policies, strategies and planning	13.2.1: Number of countries that have communicated establishment or operationalization of an integrated policy/ strategy/ plan which
SDG 13: Climate Action	Target: 502989 tCO ₂ for this monitored period	increases their ability to adapt to the adverse impacts of climate change, and foster climate resilience and low greenhouse gas emissions development in a manner that does not threaten food production (including a national adaptation plan, nationally determined contribution, national communication, biennial update report or other)
7 AFFORDABLE AND CLEAN ENERGY	By 2030, increase substantially the share of non-fossil energy in the global energy mix.	The project activity helps reducing GHG emission in power generation in the grid, which is primarily fossil fuel based.
	Target: 890577 MW _h supplied for this monitored period	
SDG 7: Affordable and Clean Energy		
8 DECENT WORK AND ECONOMIC GROWTH	8.5: By 2030, achieve full and productive employment and decent work for all women and	8.5.1: Average hourly earnings of female and male employees, by occupation, age and persons with disabilities. The project activity provides direct
	men, including for young people and persons with disabilities, and equal pay for work of equal value Target: Training, O&M staff	employment to over <u>1250</u> people. The employment involves tribal people who are more than 40% in population and also are now well qualified as well as competent to take the employment in the steel industry
SDG 8: Decent Work and Economic Growth		



Level of Assurance:

The verification report is based on the on the information collected through interviews conducted over video calls / phone calls, supporting documents provided during the verification, Project Concept Note (PCN) / Monitoring Report (MR), submitted to SQAC. The verification opinion is assured provided the credibility of all the above.

Review of the following documentation was done by SQAC Lead Verifier, Ms. Sheetal Wader, who is experienced in such projects.

Documentation Verified:

- Project Concept Note (PCN)
- Monitoring Report (MR)
- Commissioning Certificate
- Calibration report
- Deisel Register
- Steam Report
- Data provided upon request of all the documents of the related projects.

Sampling:

Not applicable

Persons interviewed:

- 1. Mr. Trinath Swain (Vice President Process): M/s Shri Bajrang Power and Ispat Limited (SBPIL).
- 2. Mr. Rajeev Lochan Upadhyay (General Manager-Power Plant): M/s Shri Bajrang Power and Ispat Limited (SBPIL).





CALIBRATION CERTIFICATE

Centre for Calibration

NAGMAN CALIBRATION SERVICES LLP
No.1887, Chemia-Bangalore National Highway,
Chembratenbaskam, Chemia-Good 123. Tamihadu, INDA
E-Mail: clcchennai@nagman.com, calibration@nagman.com
Silis: www.nagman.com



ULR-CC254822000015521F		Certificate No.: CFC2022-1209-PL/1						
Date of Issue : 09.11.2022								
		M/s. Shri Bajrang Power And Ispat Ltd.,						
Customer Name And Address		Vill. Borjhara, Urla - Guma Road,						
Customer Name And Address		Urla Growth Centre.						
		Raipur - 492 003 (C.G)						
Customer Reference		SBPIL/2022-23/825 DT. 09.08.22						
Details of the Instrument								
Location		NA						
Machine Name / Number		NA						
Description		Pressure Calibrator						
Make		Nagman®						
Model		MPC-E						
Serial Number		MPCE 0503 9355						
Identification Number		NA						
Range		Vide Respective Calibration Table						
Operating Range		NA						
Resolution		Vide Respective Calibration Table						
Accuracy		± 0.1 % F.S.						
Equipment received on		22.08.2022						
Condition of the equipment on re	eceipt	Serviced & Calibrated						
Calibration Procedure Number		CFC/WI-M03, E04						
Method of Calibration		Direct-Comparison Method						
Date of Calibration		31.10.2022						
Date of Next Calibration Suggests	ed	31.10.2023						
Calibration Environments								
Temperature		23°C ± 2°C						
Relative Humidity		35~65% RH						
Master Instrument Details	(The Standards used are t	raceable to National / International Standard	s)					
Nomenclature	Certificate No.	Validity	Traceability					
Pneumatic Dead Weight Tester	1634	31-Dec-22	MEASURE TECNIQUES					
Piston Cylinder	1500271315-1	22-Oct-24	FLUKE					
Dead Weight Tester	HT/CC/211215-10/001	15-Dec-23	HITECH					
Multifunction Calibrator	3111221-E01	26-Dec-22	NORTHLAB					

- Multimerion Calibrator 4

 Femarks

 Fema



Page 01 of 02



CALIBRATION CERTIFICATE

Centre for Calibration

NAGMAN CALIBRATION SERVICES LLP
No. 1687, Chemnal Bangalore National Highway,
Chembarandoskam, Chemnal 60 122, Tamihadu, INDIA
E-Mail: clochenasi@nagman.com, calibration@nagman.com
Site: www.nagman.com



ULR-CC254822000015560F		Certificate No.: CFC2022-1209-EL/6						
Date of Issue : 14.11.2022								
Customer Name And Address		M/s.Shri Bajrang Power and Ispat Ltd; Vill. Borjhara, Urla - Guma Road, Urla Growth Centre, Raipur - 492 003 (C.G)						
Customer Reference		DC No: SBPIL/2022-23/825	Dated: 09.08.2022					
Details of the Instrument								
Location		-						
Machine Name / Number		*						
Description		Digital Multimeter						
Make		Rishabh						
Model		RISH Multi 18S						
Serial Number		092729						
Identification Number								
Range		Vide Respective Calibration Table						
Operating Range		Economic de automotivo de securio						
Resolution		Vide Respective Calibration Table						
Input								
Output		Experience of the second secon						
Accuracy		Vide Respective Calibration Table						
Equipment received on		22.08.2022						
Condition of the equipment on:	receipt	Good						
Calibration Procedure Number		CFC/WI-E03						
Method of Calibration		Direct Method						
Date of Calibration		29.08.2022						
Date of Next Calibration Sugges	ted	29.08.2023						
Calibration Environments								
Temperature		25°C ± 4°C						
Relative Humidity		30~75% RH						
Master Instrument Details		e traceable to National / International Standards)						
Nomenclature	Certificate No.	Validity	Traceability					
Multifunction Calibrator	3111221-E01	26-Dec-22	NORTHLAB					
Multifunction Calibrator	4090921-E01	11-0ct-22	NORTHLAB					
Multifunction Calibrator	1671221-E02	17-Dec-22	NORTHLAB					

- Remarks
 1. The above UUC was calibrated at Lab.
 2. UUC is defined as Unit Under Calibration.
 3. How calibration certificate shall not be reproduced except in full without written approval of CFC.
 4. The calculated expanded uncertainty includes repeatability, resolution & uncertainty on measurements.
 5. The measurement results relate only to the tiem calibration of the content of the customer.
 6. The decision rule will be applied based on the Statement of Conformity requested by the Customer.
 7. The results are provided as observed without any adjustments.
 8. The Uncertainty stated is the expanded uncertainty of measurement obtained by multiplying the standard uncertainty by the coverage factor correspond to confidence level of 950% and the bolded letters does not meet the specified accuracy limits.

 Checked By

 Authorised Signatory



Page 01 of 05



CALIBRATION CERTIFICATE

Centre for Calibration
NAGMAN CALIBRATION SERVICES LLP
No.1687. Chemia - Bangalore National Highway.
Chembarandoskam, Chemia - 600 122. Taminadu. NDA.
E-Mail: dochema@tangnun.com. calibratlen@pangnun.com.
Silo: www.nagman.com



CC-2548

ULR-CC254822000015559F		Certificate No.: CFC2022-1209-EL,	/5					
Date of Issue : 14.11.2022		·						
		M/s.Shri Bajrang Power and Ispat Ltd	d;					
Customer Name And Address		Vill. Borjhara, Urla - Guma Road,						
customer name manaradi ess		Urla Growth Centre,						
		Raipur - 492 003 (C.G)						
Customer Reference		DC No: SBPIL/2022-23/825	Dated: 09.08.2022					
Details of the Instrument								
Location								
Machine Name / Number								
Description		Loop Calibrator						
Make		Masibus						
Model		LC 11						
Serial Number		18080332						
entification Number -								
Range		Vide Respective Calibration Table						
Operating Range								
Resolution		Vide Respective Calibration Table						
Input								
Output								
Accuracy		Vide Respective Calibration Table						
Equipment received on		22.08.2022						
Condition of the equipment on re	eceint	Good						
Calibration Procedure Number		CFC/WI-E04						
Method of Calibration		Direct Method						
Date of Calibration		29.08.2022						
Date of Next Calibration Suggest	ed	29.08.2023						
Calibration Environments								
Temperature		25°C ± 4°C						
Relative Humidity		30~75% RH						
Master Instrument Details	(The Standards used a	are traceable to National / International	Standards)					
Nomenclature	Certificate No.	Validity	Traceability					
Multifunction Calibrator	1671221-E02	17-Dec-22	NORTHLAB					
Multifunction Calibrator	3111221-E01	26-Dec-22	NORTHLAB					

- 1. The above UUC was calibrated at Lab. 2. UUC is defined as Unit Under Calibration.

- 2. UUC is defined as Unit Under Calibration.
 3. The calibration certificate shall not be reproduced except in full without written approval of CFC.
 4. The calculated expanded uncertainty includes repeatability, resolution & uncertainty on measurements.
 5. The measurement results relate only to the item calibrated.
 6. The decision note will be applied based on the Statement of Confirmity requested by the Customer.
 7. The results are provided as observed without any adjustments.
 8. The Uncertainty stated is the expanded uncertainty of measurement obtained by multiplying the standard uncertainty by the coverage factor correspond to confidence level of 95%.
 9. The results are found compliance to manufacturer specifications and the bolded letters does not meet the specified accuracy limits.

 Checked By

 Authorised Signatory

E.Sajitha Team Member



D.Arun Team Leader

Page 01 of 02

0.00 O- 25.00 3.7	57 gs/Sq.C 25% of F 6092729 05 % of F 7 - 1 7 -	INSTITUTE OF THE PROPERTY OF T	1. COMPA 1. DIGITAL RUMENT UN 2. 2. 2. CALIBRAL MIGITAL MI	CALIB TION R ULTIME	BRATED BY : M/ BRATION DUE O IFICATE NO. : 2 IMETER IRATED BY : M/ IRATION DUE O CALIBRATION : 1 TYPE : IRACY :± O ERACY :± O ERACY :± O ERACY := FORM	S NAGMAN INST. (P) LTD. CHENNA IN: 24-08-2022 0021-22/CFC/997/4 S NAGMAN INST. (P) LTD. CHENNAI N: 01-09-2022 0021-22/CFC/997/5
SR. NO.: REE 000 RANGE: 0-160 K; ACCURACY: ± 0.2 MAKE: RISHAB MODEL: RISHAB SR. NO.: 92729 ACCURACY: +1-0.4 TAG NO.: 11 P ESCRIPTION: £ CALIBRATION DA PRESS INPUT IN % RESS 0.0.0 0.00 0.00 3.3	57 gs/Sq.C 25% of F 6092729 05 % of F 7 - 1 7 -	F.S. INSTI	1.DIGITAL RUMENT UN TX. 2. 2. CALIBRA DIGITAL MI	CALIB CALIB CALIB CALIB CALIB CALIB CALIB CALIB CALIB CERTI NDER C INPUT ACCU MAKE CALIB TION R	BRATED BY : M/ BRATION DUE O IFICATE NO. : 2 IMETER IRATED BY : M/ IRATION DUE O CALIBRATION : 1 TYPE : IRACY :± O ERACY :± O ERACY :± O ERACY := FORM	S NAGMAN INST. (P) LTD. CHENNA N: 24-08-2022 2021-22/CFC/997/4 S NAGMAN INST. (P) LTD. CHENNA N: 01-09-2022 2021-22/CFC/997/5 : 01 S 7.
SR. NO.: REE 000 RANGE: 0-160 K; ACCURACY:± 0.2 MAKE: RISHAB MAKE: RISHAB SR. NO.: 92729 ACCURACY: +1-0.4 TAG NO.: 11 P ESCRIPTION: F UNGE: O CALIBRATION DA RESSON	57 gs/Sq.C 25% of F 6092729 05 % of F 7 - 1 7 -	F.S. INSTI	RUMENT UN	CALIB CALIB CALIB CALIB CALIB CERTI NDER CI INPUT ACCU MAKE CALIE TION R	METER METER MATER BY: M/ METER MATER BY: M/ MATER BY:	N: 24-08-2022 8021-22/CFC/997/4 S NAGMAN INST. (P) LTD. CHENNAI N: 01-09-2022 1021-22/CFC/997/5 :
RANGE: 0-160 Kg ACCURACY: ± 0.2 MAKE: RISHAB MODEL: RISH 18 s SR. NO: 92729 ACCURACY: +/- 0.4 TAG NO.: 11 P ESCRIPTION: NGE: O CALIBRATION DA RESTORMENT	gs/Sq.C 25% of F 092729 05 % of F T - 1 TE: /	F.S. INSTI	RUMENT UN	CALIB CALIB CALIB CALIB CALIB CERTI NDER CI INPUT ACCU MAKE CALIE TION R	METER METER MATER BY: M/ METER MATER BY: M/ MATER BY:	N: 24-08-2022 8021-22/CFC/997/4 S NAGMAN INST. (P) LTD. CHENNAI N: 01-09-2022 1021-22/CFC/997/5 :
ACCURACY : ± 0.2 MAKE : RISHAB MODEL : RISH 18 S SR. NO. : 92729 ACCURACY : +1-0.4 TAG NO.: 11 P ESCRIPTION : F NGE : O CALIBRATION DA NPUT IN % RES/50 0.00 25.00 37	092729 05 % of F T - 1 TE: / I	F.S. INSTI	RUMENT UN	CALIB CALIB CALIB CALIB CERTI NDER C INPUT ACCU MAKE CALIB TION R	METER RATED BY: MANAGE RATION DUE O FICATE NO.: 2 CALIBRATION I TYPE: RACY:± O C: ROSOU ENTATION DUE EPORT ETER IN MA	S NAGMAN INST. (P) LTD. CHENNAI N: 01-09-2022 021-22/CFC/997/5 :
MAKE: RISHAB MODEL: RISH 18 S SR. NO.: 92729 ACCURACY: +1-0.4 TAG NO.: 11 P ESCRIPTION: F UNGE: O CALIBRATION DA CALIBRATION DA RESTORMENT REST	092729 05 % of F T - 1 TE: 1 TE: 1 TRAIN RATOR ROGIN R.COR	F.S. INSTI	RUMENT UN	CALIB CALIB CERTI NDER C INPUT ACCU MAKE CALIB TION R	RATED BY : MARTIN DUE OF FICATE NO.: 2 CALIBRATION : TYPE: RACY: ± O CRATION DUE CRATION DUE	N: 01-09-2022 021-22/CFC/997/5 :
MODEL: RISH 18 S SR. NO.: 92729 ACCURACY: +/- 0.4 TAG NO.: 11 P ESCRIPTION: F LINGE:	O5 % of F	INSTITUTE OF THE PROPERTY OF T	RUMENT UN	CALIB CALIB CERTI NDER C INPUT ACCU MAKE CALIB TION R	RATED BY : MARTIN DUE OF FICATE NO.: 2 CALIBRATION : TYPE: RACY: ± O CRATION DUE CRATION DUE	N: 01-09-2022 021-22/CFC/997/5 :
MODEL: RISH 18 S SR. NO.: 92729 ACCURACY: +/- 0.4 TAG NO.: 11 P ESCRIPTION: F LINGE:	O5 % of F	INSTITUTE OF THE PROPERTY OF T	CALIBRA	CALIB CERTI NDER CO INPUT ACCU MAKE CALIE TION R	RATION DUE O FICATE NO.: 2 CALIBRATION TYPE: RACY:± BRATION DUE EPORT ETER IN MA	N: 01-09-2022 021-22/CFC/997/5 :
SR. NO.: 92729 ACCURACY: +1-0.4 TAG NO.: 1 P ESCRIPTION: F (NGE: O CALIBRATION DA NPUT IN % PRESS AUBB NPUT IN % 0.00 0.00 25.00 3 3	O5 % of F	INSTITUTE OF THE PROPERTY OF T	CALIBRA	DER COUNTY ACCUMAKE CALIE	ALIBRATION TYPE: RACY:± 0 RACY:± 0 RACY:± 0 RATION DUE EPORT ETER IN MA	1021-22/CFC/997/5 : - - - の子ミゲ. - - かんれた :) S・0 プ・2.023
TAG NO.: 1 P ESCRIPTION: F INGE: O CALIBRATION DA PRESS NPUT IN % READIN 10.00 0 25.00 3 3	T - 1 Peed L TE: 1 IN RATOR NG IN RATOR RATOR RETER RET RETER RETER RETER RETER RETER RETER RETER RETER RETER	INSTITUTE OF THE PROPERTY OF T	CALIBRA	MAKE CALIE TION R	ALIBRATION TYPE: IRACY:± 0 ERACY:± 0 BRATION DUE EPORT ETER IN MA	:- -0757, mount:: 15.07.2023
TAG NO.: 1 P ESCRIPTION : F INGE : O CALIBRATION DA NPUT IN % READING 0.00 Ø 25.00 3 3	T - 1 Peed L TE: 1 IN RATOR NG IN RATOR RATOR RETER RET RETER RETER RETER RETER RETER RETER RETER RETER RETER	INSTITUTE OF THE PROPERTY OF T	CALIBRA	MAKE CALIE TION R	TTYPE: PRACY:± 0 ROSe 0 RATION DUE EPORT ETER IN MA	-0757, mount: : 15.07.2023
ESCRIPTION : F INGE : O CALIBRATION DA NPUT IN % CALIBRATION REAPON REAPON 0.00 0 25.00 3 7	TE: I	READING OF	CALIBRA	MAKE CALIE TION R	TTYPE: PRACY:± 0 ROSe 0 RATION DUE EPORT ETER IN MA	-0757, mount: : 15.07.2023
ESCRIPTION : F INGE : O CALIBRATION DA NPUT IN % CALIBRATION REAPON REAPON 0.00 0 25.00 3 7	TE: I	READING OF	CALIBRA DIGITAL MI	MAKE CALIE TION R	RACY:± 0 RACY:± 0 RATION DUE EPORT ETER IN MA	mahnt: 15.07.2023
NPUT IN % PRESS 0.00 0.00 0.25.00 3.7	IN RATOR ROGIN ROGIN ROGIN ROGIN	READING OF	CALIBRA DIGITAL MI	MAKE CALIE TION R ULTIME	ROSAL BRATION DUE EPORT ETER IN MA	mahnt: 15.07.2023
NPUT IN % PRESS 0.00 0.00 0.25.00 3.7	IN RATOR ROGIN ROGIN ROGIN ROGIN	READING OF	CALIBRA	MAKE CALIE TION R ULTIME	ROSAL BRATION DUE EPORT ETER IN MA	mahnt: 15.07.2023
NPUT IN % CALIBRATION DA: NPUT IN % CALIBRA READII KES/59 0.00 Ø- 25.00 3.7	IN RATOR NG IN R.Cm	READING OF	CALIBRA DIGITAL MI	CALIE TION R ULTIME	EPORT ETER IN mA	: 15.07.2023
0.00 0- 25.00 3.7	NG IN R	REQD. VALUE	DIGITAL MI	ULTIME	TER IN mA	DEMARKS
0.00 0- 25.00 3.7	NG IN R	REQD. VALUE				DEMARKS
0.00 O- 25.00 3.7	a.Cm		ACTUAL V			
25.00 37	.0			ALUE	DEVIATION	REMARKS
		4.00	4.01		0.01	
	2.	8.00	8.01		0.01	
	5.0	12.00	12.00			
	.5	16.00	16.00			
100.00 15	0.0	20.00	80.00			
			RUMENT UN	_	ALIBRATION:	
AG NO.: 11 P					TYPE: -	
ESCRIPTION: S	team	POPSSUMP	TX.		RACY:± 0	
ANGE: 0	~ 1:	SO KAlcmi	L		: Rose	
ALIBRATION DAT	TE: 1	5.07.202				15.07.2023
IPRESS N			CALIBRAT			
NPUT IN % CALIBRO	ATOR D	READING OF				REMARKS
0.00 ©	.Cm	4.00				
	.5	8.00	4.0		4 - 1	
	.0	12.00	8.0		0.01	
75.00 112		16.00	12,0			
11.50			16.0	_		
100.00 150	0.0	20.00	20.0	~		~80

Signature is not required as it is generated through software



MAKE : YA SR. NO. : F RANGE : 0			1. COMPA	RATO	PCALICE	•	
SR. NO. : F RANGE : 0					N GAUGE		
RANGE: 0		200 1 30	0.00	CALI	BRATED BY:	M/S NAGMAN INST. (P) LTD. CHENNA	
						ON : 24-08-2022	
				CERT	TIFICATE NO. :	2021-22/CFC/997/4	
ACCURAC	Y:± 0.25%	of F.S.					
			1.DIGITAL	L MULT	IMETER		
MAKE : RISI				CALIE	BRATED BY : N	I/S NAGMAN INST. (P) LTD. CHENNA	
MODEL : RIS		729		CALIE	BRATION DUE	ON: 01-09-2022	
SR. NO. : 92	-			CERT	IFICATE NO. :	2021-22/CFC/997/5	
ACCURACY	: +/- 0.05 %						
	10		TRUMENT UN	NDER (CALIBRATION	1:	
TAG NO.:		0010 - T				-	
ESCRIPTION	DN: Ste	AM Pro TX.	TO 1/L	ACCU	JRACY :± (0.075 %	
RANGE:	0~	100 KAlcm	2	MAKE	: ABB		
CALIBRATIC	ON DATE :	18.07.20	22	CALIBRATION DUE: 18.07.2022			
	PRESS IN	T	CALIBRAT				
INPUT IN %	CALIBRATOR READING IN Kgs/Sq.Cm	READING OF	-	DEVIATION	REMARKS		
0.00	Rgs/3q.Cm	4.00	4.00				
25.00	85	8.00			-		
50.00	50	12.00	18.00				
75.00	75	16.00	16.01				
100.00	100	20.00	80.00		0.01		
					ALIBRATION		
TAG NO.:	~				TYPE:	V	
DESCRIPTIO	N:				RACY:+		
RANGE :				MAKE			
CALIBRATIO	N DATE :	_			RATION DUE		
			CALIBRATI				
	PRESS IN CALIBRATOR	READING OF	DIGITAL MUI	LTIME	TER IN mA		
INPUT IN %	READING IN Kgs/Sq.Cm	REQD. VALUE	ACTUAL VA			REMARKS	
0.00		4.00					
25.00		8.00					
50.00		12.00			1		
		16.00					
75.00 100.00		20.00				1	

Sr.	Meter Sr. no.	Make	Accuracy Class	Specification
1.	120445/20097- 1707	Conzerv	0.5	Current Details:-/1 or 5A Voltage Details:80 to 600V
2.	213797/3739- 2411	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
3.	213797/3743- 2411	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
4.	213797/3744- 2411	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
5.	213797/3741- 2411	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
6.	120445/20103- 1707	Conzerv	0.5	Current Details:-/1 or 5A Voltage Details:80 to 600V
7.	34133841020	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
8.	34133841017	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
9.	126752/231- 2907	Conzerv	0.5	Current Details:-/1 or 5A Voltage Details:80 to 600V
10.	213797/3742- 2411	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
11.	34133841018	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
12.	213797/3746- 2411	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
13.	34133820512	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
14.	213797/3737- 2411	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
15.	213797/3740- 2411	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
16.	214017/3835- 2511	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V
7.	34120540821	Conzerv /Schneider	0.5	Current Details:50mA to 6A, Voltage Details:80 to 600V

		SHREE BAJRANG POV	VER AND	ISPAT	ITD								
Report Time Report Date		Jan - 22 CREE		101711	LID			_	_				
LNO	TAG	DESCRIPTION	UNIT						*				
	_		UNII	0 HR	-1 HR	2HR	JHR	4HR	-5HR	-6 HR	-7 HR	AVERAGE	
1	\$833170101	Feed Water Temperature	Deg C	106.94	106.64	106.94	107 07						
2	\$833PT0101	Feed Water Pressure	Kolom2	69.77	70.62	70.20		1000.0	106.84	144.01	-		1
3	SB33FT102	Feed Water Flow -2	TPH	49.09	45.04		70.62	-	89.95			70.33	
4	SB33TT204	Main Steam Temperature	Deg.C	497.99	491.44		100.00	10.76	45.44	91.00	10.00	48.52	
5	S833PT202	Main Steam Pressure-1	Kalon2	65.08					488.07		100110	492.32	
6	S833FT202	Main Steam Flow-2	TPH	53.24	66.15			99(1)	65.65	88.65	65.11	65.78	
7:	COMP_SB33FT202	Compensated Main Steam Flow-2	TPH		50.92	51.39	10.71	51.87	49.57	54.59	50.59	51.89	
8	SB33MW	MW Generation	MW	52.58	51.18	51.22		52.33	50.17	55.00	50.41	52.01	
9	S833PT_0100	TURBINE INLET PRESSURE		7.60	7.63	7.37	7.55	7.30	7.58	7.48	7.52	7.50	
10	S833TT_0103	TURBINE INLET TEMPRATURE	Kglon2	64.03	65.24	64.75	64.97	64.79	64.71	85.58	64.11	64.77	
11	SB33FT_0100	TURBNE INLET FLOW	Deg C	492.07	489.60	486.23	486.67	491.42	490.69	496.15	485.54	489.80	
12	COMP_SB33FT0100	TURBINE INLET COMPENSATED FLOW	TPH	32.18	32.30	31.11	32.04	31,15	32.23	31.56	32.27	31.86	
		TOTALISER	TPH	31.98	32.53	31.65	32.44	31.83	32.51	32.00	32.51	32.18	
		IUTALISER											TOT RESET ON
1	\$833FT102_TOT	Feed Water Flow 2 Totaliser-ACCM	-										31/01/2022 AT 60:0 Hrs.
	COMP_SB33FT202 TOT	Comp. Main Steam Flow -2 Totaliser -ACCM	TONS	279.87	232.04	182.09	130.75	77.65	26.28	36833.44	36782.14		36856.66
	COMP_SB33FT0100_TOT		TONS	285.92	235.78	185.94	133,39	79.07	26,47	37611.29	37558.81		37636.37
	SB33 MW TOTL	Compensated Turbine Inlet Flow Totaliser -ACCM	TONS	177.31	144.95	112.81	80.63	48.34	15,09	23882.37	23850.05		23898.62
		MNN TOTALISER-ACCM (Ref. Energy Mtr.)	MW	41.33	33.78	26,28	18,77	11.25			5567.70		5579.00

RAPUR,	cg.												
REPORT	FOR CREDA-1 & 2	PARAMETERS											
SHFT - A	4/8/C												
IR. NO.	740	DESCRIPTION	UNIT	OHr	- 1Hr	-2Hr	-3Hr	-4Hr	-514:	404	-7Hr	8990	
SR. NO.	TAG	DESCRIPTION	UNIT	OH	-100	-2711	-2111	-Arti	orn	-			TOT RESET ON 31/01/22 AT 00:00
	1 11PT1750	FEED WIR PR ECO	KG/CM2	69.9	71.2	69.8	69.4	69.3	69.3	69.2	69.2	69.7	Hrs.
	2 11TT-1710	FEED WITH TEMP	DEG C	105.5	105.4	105.3	105.4	105.3	105.4	105.4	105.4	105.4	Person.
	3 11FT_1709	FEED WTR FL	TPH	26	26.1	25.1	24.2	23.9	24	23.6	24.2	24.6	
	4 11BFW_TOT_A	FEED WTR FL TOT_A	TON	134.8	109.8	83.7	59	35.5	11.6	18395.5	18371.8		18407.1
	5 11PT_1728	MAIN STM PR	KG/CM2	68.6	69.7	68.5	68.2	68.1	68.1	68	67.9	68.4	
	6 11TT_1730	MAIN STM TEMP	DEG C	506.8	509.5	507.3	499.1	495	495 25.7	493	498.6 25.7	500.5	
	7 11FT_1729C	MAIN STM FL (C)	TPH	27.7	31.6	20.8	26	28.4	12.8	19584.8	19559.6	20.0	19597.6
	8 11STM_TOTC_A	MAIN STM FL TOT (C)_A	TON	144.9	121.0	90	63.6	36.4	12.6	19004.8	19009.0		1999.4
	1 22PT1750	FEED WTB PR ECO	колома	69.4	70.1	69.2	68.9	69.1	69.2	69.5	69.4	69.3	
	2 22TT-1710	FEED WTR TEMP	DEG C	106.3	106.3	106.1	105.3	106.2	106.2	108.2	105.2	105.2	
	3 22FT_1709	FEED WIR FL	TPH	25.7	24.6	23.7	23.6	25.3	24.8	26.2	27.2	25.1	1000000
	4 228FW_TOT_A	FEED WTR FL TOT_A	TON	133.7	109.5	84.9	61.3	37.7	12.4	18876.2	18849.7		18888.6
	5 22PT_1728	MAIN STM PR	KG/CM2	66.1	66.8	66	65.8	65.9	- 65	495.5	66	66.1	
	6 22TT_1730	MAIN STM TEMP	DEG C	495.6	491.9	495.3	493.5	497.8	497.8	490.0 26.7	493.2	26.2	
	7 22FT_1729C	MAIN STM FL (C)	TON	26.6	27.1	24.8 67.7	63.3	39	13	19475.4	19448	20.2	19455.4
	8 2251M_101C_A	MAIN STM FL TOT (C)_A	TON	130.4	114.0	07.7	63.3		14	19410.4	15449		13400.4
	1 TG1_MW	TG1 PWR GEN	MW	7.6	7.6	7.6	7.6	7.6	7.6	7.6	7.6	7.6	
		TG1 MW TOT_A (Ref Energy Mtr)	MWH.	41.8	34.2	26.6	19	11.4	3.8	5601.3	5593.7	040000	5605.1
	3 11PT_0100	MAIN STM PR	KG/CM2	64.6	65.3	64.7	64.4	64.4	64.5	64.4	64.3	64.6 488.9	
	4 11TT_0100	MAIN STM TEMP	DEG C	491.9	497.1	491.4	486.3	487.2	486.7	30.7	30.6	30.5	
	5 11FT_0100 C	MAIN STM FL (C)	TPH	30.2	30.2 136.1	105.9	20.6 75.8	30.5	15.3	22255.4	22225	30.6	22270.7
	6 TISTM_TOT_C_A	MAIN STM TOT (C)_A	TON	105.7	130.1	100.9	70.0	40.0	10.0	22000.4	22220		222707
	1 TG2 MW	TG2 PWR GEN	MW	9.5	9.6	9.5	9.5	9.5	9.5	9.4	9.5	9.5	
	2 TG2 MW TOT A	TG2 MW TOT, A (Ref Energy Mb)	MWH	52.4	42.9	33.3	23.8	14.3	4.8	7036	7028.5		7040.8
	3 22PT_0100	MAIN STM PR	KG/CM2	64.5	65.2	54.5	64.3	64.3	64.3	64.3	64.2	64.5	
	4 22TT_0100	MAIN STM TEMP	DEG C	490.0	493.5	490.1	487.8	488.9	488.5	487.6	487.5	489.3	
	8 22FT_0100 C	MAIN STM FL (C)	TPH	40.7	41.1	40.7 140.7	100.6	40.5 80.4	40.6 20.2	40.4 29801.6	29761.4	40.6	29821.8
	6 22STM TOT_C_A	MAIN STM TOT (C)_A	TON	221.3	181.8	140.7	100.5	80.4	20.2	29001.0	29//01/4		ADDA 1.0


EXECUTIVE ENGINEER (MT) DN. I.

-	_							-10	IOFAI		SHREE BAJRANG POW		411
											JUNE 17 CREDA	05.30AM 01/07/2017	Report Time Report Date
	AVERAGE	7HR	€HR	SHR.	4HR	SHR .	2HR -	HR .	OHR .	UNIT	DESCRIPTION	TAG	SR.NO
8	109.08	108.98	109.20	109,10	109.10	108.98	109.10	109.15	109.07	Deg.C	Feed Water Temperature	S833TT0101	1
4	71,64	71.43	71.51	71.46	71.11	71.89	72.12	72.12	71.51	Kglan2	Food Water Pressure	S833PT0101	2
4	58.30	56.86	58.65	58,95	58.68	58.33	80,33	58.12	56,47	TPH	Feed Water Flow -2	S833FT102	3
		500.03	499.78	499.78	501.04	438.66	503.19	503.58	497.75	Deg.C	Main Steam Temperature	S833TT204	4
4	85.94	65.83	65.78	65.65	65.35	66.20	65.25	66.38	66,07	Kglon2	Main Steam Pressure-1	S833PT202	5
4	59.84	59.71	59.99	60.31	60.38	59.16	60.68	60.18	58.28	TPH	Main Steam Flow-2	S833FT202	6
1	59.81	59.59	/ 60.12	60.11	59.99	59.52	60.79	50.14	58.22	TPH	Compensated Main Steam Flow-2	COMP_S833FT202	7
4	7.42	7.46	7,40	7.33	7.46	7.27	7,50	7.47	7.46	MW	MW Generation	SB33MW	8
8	14.50	64.49	64.49	64.37	64.03	64.97	64.95	65.09	64.86	Kglon2	TURBINE INLET PRESSURE	SB33PT_0100	9
4	A69.37	488.91	488.26	490.27	488.47	488.26	490.72	491.86	488.26	Deg.C	TURBINE INLET TEMPRATURE	SB33TT_0103	10
4		31.26	31.03	30.63	31.42	30.34	31.18	31.04	31.04	TPH	TURBINE INLET FLOW	SB33FT_0100	- 11
	31.25	31.55	31.42	30.78	31.61	30.75	31.49	31.16	31.22	TPH	TURBINE INLET COMPENSATED FLOW	COMP_SB33FT0100	12
TOT RESET ON 30/06/2017 AT 00:0 Hrs.											TOTALISER		
40178.57		40089.93	40149.09	29.50	88.75	148.10	206.53	264.02	321,81	TONS	Feed Water Flow 2 Total ser-ACCM	SB33FT102_TOT	1
40929.67		40839.25	40899.62	30.08	90.50	150.98	210.61	269.17	327.95	TONS	Corrp. Main Steam Flow -2 Totaliser -ACCM	COMP SB33FT202 TOT	2
22659.30		22612.15	22643.91	15.53	46.51	77.51	109.20	141.01	172.86	TONS	Compensated Turbine Inlet Flow Totaliser -ACCM	COMP_S833FT0100_TOT	3
5339.65		5328.47	5335.99	3.68	11.00	18.34	25.83	33.35	40.89	MW	MW TOTALISER-ACCM (Ref. Energy Mtr.)	SB33 MW TOTL	

	SHREE	AFO1 2017 05:30:01 BAJRANG POWER	AND ISPAT LTD.	June 1	7									
					100									
		T FOR CREDA-1 &	PARAMETERS											
	SHFT.	A/B/C												
	SR. NO	TAG	DESCRIPTION	UNIT	OHr	dHr	-219	-39+	-694	-614	-8Hr	-714	EVQ.	
		1.11PT1250	FEED WTR PR ECO										200	TOT RESET ON 20/06/17 AT
		2 11TT-1710	FEED WTR PR ECO FEED WTR TEMP	KG/CM2	107.9	108	68.7	108.1	68.8	68.8	68.8	668	68.9	90:00 Hrs.
		3 11ET 1700	FEED WIR FL	TPH	22.9	22.5	20	21.5	21.8	108.1	108	108.3	108.1 22.1	
	2-1	4 118FW_TOT_A	FEED WTR FL TOT A	TON	118.7	98.5	73.5	53.7	32.1	10.9	15990.5	15968.2	22.1	16001.65
,	~ '		MAIN STM PR	KG/CM2	66.2	65.9	65.6	65.6	65.6	65.6	65.6	65.5	65.7	10201.65
		6 11TT_1730 7 11FT_1729C	MAIN STM TEMP	DEG C	498	494.9	490.4	494.2	494.5	496.9	494	495.8	494.0	
			MAIN STM FL (C) MAIN STM FL TOT (C) A	TPH	23.1	102.3	21.7	22.8	22.9	23.5	23.5	24.1	23.2	
		e manacionaça	and share for (o) A	100	A 123.7	102.3	78.3	55.7	33.8	11.4	16834	16810.6		16845.75
		1 22PT1750	FEED WTR PR ECO	KG/CM2	68.3	67.7	67.6	67.2	67.3	67.2	67.2	67.1	67.5	
. 7	V	2 22TT-1710	FEED WIR TEMP	DEG C	108.6	103.6	108.5	108.5	108.6	108.6	108.5	108.6	108.6	
0		3 22FT_1709 4 228FW TOT A	FEED WTR FL	TPH	16	16.3	16.1	13.1	15.2	14.7	14.1	14.3	15.0	
		4 228FW_TOT_A 5 22PT_1728	FEED WTR FL TOT_A	TON	86.9	68.1	51.0	35.4	21.2	7.0	12325.9	12311.5		12333.25
		6 22TT 1730	MAIN STM TEMP	DEGIC	504.9	492.2	494.3	64.9	64.9	64.0	64.8 488.1	64.7	65.0	
		7 22FT_1729C	MAIN STM FL (C)	TPH	19.5	16.0	17.2	14.9	15.7	15.6	15.3	478.8	491.3	
		B 22STM_TOTC_A	MAIN STM FL TOT (C)_A	TON	92.2	72.6	55.3	38.1	22.7	7.9	13131.2	13116.1	19.0	13139
					_									
		1 TG1_MW 2 TG1_MW_TOT_A	TG1 PWR GEN TG1 MW TOT A (Ref Energy Mtr	MVV	7.4	30.6	6.7	16.7	6.8	6.6	6.6	6.6	6.8	
(6	1	3 11PT 0100	MAIN STM PR	KGICMS	64.6	64.3	64.7	64.1	64.1	3.5 64.1	64	4754.4	64.2	4764.3
/-		4 11TT_0100	MAIN STM TEMP	DEG C	485.6	482	481.4	450.3	482 B	482.1	478.7	478.3	481.4	
		5 11FT_0100 C	MAIN STM FL (C)	TPH	30	28.2	27.4	27	27.5	26.9	26.8	27.1	27.6	
		6 TISTM_TOT_C_A	MAIN STM TOT (C)_A	TON	151.9	122.5	94.9	66.9	40.6	13.8	19167.4	19140.8		19180.85
	01	1 TG2_MW	TG2 PWR GEN	MW	9.6	9.4	9.3	9.3	9.2	9.6	9.2	9.3	9.4	
21	·V	2 TG2_MW_TOT_A	TG2 MW TOT_A (Ref Energy Mr.)		51.4	41.9	32.4	23.1	13.8	4.5	6713.8	6704.5	2,4	6718.55
1	2	3 22PT_0100 4 22TT_0100	MAIN STM PR MAIN STM TEMP	KG/CM2	64.5	64.1	64	63.9	63.9	63.8	63.8	63.7	64.0	
-		5 22FT 0100 C	MAIN STM TEMP MAIN STM FL (C)	DEG C	493.8	490.7 38.8	490.4	490.2	491	490,7	488.4	489.2	490.6	
		6 22STM TOT C A	MAIN STM TOT (C) A	TON	215.3	175.6	135.6	39.2 95.4	38.9 57.6	18.8	38.7	39.3	39.5	
		0		0.000	-		100.00	-0.4	27.0	10.0	amed! if	49166.2		28247.2





	0	m Generation	o fin Yours	REPORT FO				# W		
Day	WHR1	WHR2	Rice Husk Fired AFBC Boiler	Total Steam Generation	T.G. 1	T.G. 2	T.G. 3	Total Steam Consumption	Dumped Steam	Net Use Steam from AFBC
	A	В	c	D=A+B+C	E	F	G	H=E+F+G	I=D-H	J=C-I
01 January 2011 (00:00 Hrs to 05:30 Hrs)			328.86	472.26				463.22	9.04	
01-Jan-18	0.30	647.50	1.431.94	2.079.74	526.20	852.10	661.28	2.039.58	40.16	1.391
02-Jan-18	0.20	644.80	1.440.76	2,085,76	513.30	856.20		2.043.47	42.29	
03-Jan-18	140.70	656.90	1,419.35	2,216.95				2,153.44	63.51	1,355
04-Jan-18	403.80	662.60	1,275.33	2,341.73				2,300.31	41.42	1,233
05-Jan-18	349.20		680.61	1,571.31	591.50	480.20	417.66	1,489.36	81.95	598
~96-Jan-18	374.20		686.16	1,624.46	559.00	509.10	469.69	1,537.79	86.67	599
7-Jan-18	441.10		1,325.77	2,421.37	691.20	892.80	788.37	2,372.37	49.00	1,276
08-Jan-18	480.80		1,332.00	2,469.30	727.80		791.52	2,447.92	21.38	1,310
09-Jan-18	480.10		1,341.24	2,453.74			786.86	2,436.66	17.08	1,324
10-Jan-18	502.10		1,333.27	2,457.77	725.00		790.02	2,442.42	15.35	1,317
11-Jan-18	519.60		1,301.65	2,444.15			792.38	2,429.08	15.07	1,286
12-Jan-18	554.30	605.80	1,290.65	2,450.75			793.46	2,434.26	16.49	1,274.
13-Jan-18	544.40	600.00	1,305.87	2,450.27			790.28	2,431.78	18.49	1,287
14-Jan-18	531.40	606.00	1,306.97	2,444.37	720.10	916.60	792.05	2,428.75	15.62	1,291.
15-Jan-18	491.00	693.90	1,251.15	2,436.05	696.10	927.80	791.43	2,415.33	20.72	1,230.
16-Jan-18	474.10	641.00	1,304.13	2,419.23	693.80		772.65	2,397.85	21.38	1,282.
17-Jan-18 18-Jan-18	455.90	669.40	1,343.80	2,469.10	705.20		788.34	2,449.44	19.66	1,324.
18-Jan-18 19-Jan-18	477.10 539.80	667.20 679.20	1,322.76	2,467.06	704.10	949.80	792.09	2,445.99	21.07	1,301.
19-Jan-18 20-Jan-18	578.20		1,247.49	2,466.49	707.20	951.10	790.55	2,448.85	17.64	1,229
20-Jan-18 21-Jan-18	584.20	663.90 649.30	1,243.92	2,486.02	715.80	963.20	784.09	2,463.09	22.93	1,220.
22-Jan-18	535.80	641.20	1,263.69	2,497.19	718.80	966.50	793.26	2,478.56	18.63	1,245.
23-Jan-18	603.30	670.30	1,287.59	2,464.59 2,490.68	708.20 717.20	953.70	778.79	2,440.69	23.90	1,263.
23-Jan-18 24-Jan-18	628.60	626.90	1,217.08	2,490.68		967.40	784.96	2,469.56	21.12	1,195.
25-Jan-18	593.40	578.60	1,215.11	2,470,61	701.70 715.20	961.50	779.85	2,443.05	27.56	1,187.
26-Jan-18	645.90	645.90	1,175.87	2,347.87	715.20	824.50	777.55	2,317.25	30.62	1,145.
27-Jan-18	635.40	626.90	1,183.19	2,474.99	719.20	954.30 965.10	775.59	2,449.09	25.90	1,157.
28-Jan-18	632.00	669.70	1,229.62	2,491.92	717.20	965.10	784.35 784.29	2,466.65	25.27	1,204.
-39-Jan-18	638.60	659.00	1,205.96	2,508.16	725.00	968.90	784.29	2,477.59	30.59	1,175.
-Jan-18	609.10	625.30	1,135.12	2,369.52	661.50	927.90	751.55	2,473.23	30.33	1,175.6
31- January-2018 (upto 24:00 Hrs)	439.45	454.10	916.24	1,809.79	497.90	693.15	592.67	1,783.72	28.57	1,106.5
TOTAL	14,884.15	19,723.00	38,549.63	73,156.78	21 179 60	27 830 05	23 202 65	72,211.30	945,48	





















Applied methodologies and standardized baselines:

UCR Protocol Standard Baseline

SECTORAL SCOPE - 01 Energy industries (Renewable/Non-renewable Sources)

04 Manufacturing industries

TYPE III - Energy Efficiency

CATEGORY - ACM0012 Large-scale Consolidated Methodology - Waste energy recovery Version 06.0

The consolidated methodology is applicable to project activities implemented in an existing or Greenfield waste energy generation (WEG) facility converting waste energy carried in identified waste



energy carrying medium (WECM) stream(s) into useful energy (i.e. power, mechanical or thermal) consumed in an existing or Greenfield recipient facility(ies) and/or supplied to the grid in the case of electricity generation. The WEG facility may be one of the recipient facilities.

Applicability of methodologies and standardized baselines

- This project is included under this methodology since it applies to project activities that generate electricity from waste heat or the combustion of waste gases in industrial facilities. It's also included within the UCR Standard Positive List of technologies (updated) and is within the large -scale CDM thresholds under the applied methodology.
- Project activity involves power generation with installed capacity of 18 MW (8 MW+10 MW). Regulations do not require the project activity to recover and/or utilize the waste energy prior to the implementation of the project activity; The methodology is applicable where waste pressure is used to generate electricity only and the electricity generated from waste pressure is measurable.
- The proposed project activity is a power generation project from waste heat from DRI kilns in a sponge iron plant. The project activity displaces Chhattisgarh State Electricity Board (CSEB) grid power, part of WR grid, which is predominantly fossil fuel based.
- The methodology allows for the recipient facility to be same as the waste energy generation facility. The project site is the waste energy generation facility and the facility itself receives useful energy generated using waste energy under the project activity.

Applicability of double counting emission reductions

There is no double accounting of emission reductions in the project activity due to the following reasons:

- Project is uniquely identifiable based on its location coordinates,
- Project has dedicated commissioning certificate and connection point and plant operation data on power generation in project activity is taken from energy meters installed at project site.
- Project is associated with distinct and unique energy meters which are dedicated to the consumption point for PP.



Agreement for Double Counting Avoidance from Proponent has been provided duly signed on 07/03/2024


Project boundary, sources and greenhouse gases (GHGs)

The spatial extent of the project boundary comprises the waste heat or gas sources, captive power generating equipment, any equipment used to provide auxiliary heat to the waste heat recovery process, and the power plants connected physically to the electricity grid that the proposed project activity will affect. In line with the methodology the project boundary encompasses emissions of the project activity associated with the CO_2 emissions from the combustion of auxiliary fossil fuels and baseline emissions associated with the CO_2 emissions from fossil fuel fired power plants connected to the electricity system.

At the project site there is captive power generating equipment but there is no injection of fuel into the after burning chamber to provide auxiliary heat. The project boundary is hence the spatial extent to the captive power generating equipments and the power plants connected to the grid.

	Source	GHG	Included?	Justification/Explanation
		CO ₂	Included	Major source of emission
Baseline	Grid- connected	CH ₄	Excluded	Excluded for simplification. This is conservative.
	electricity	N ₂ O	Excluded	Excluded for simplification. This is conservative.
Project Activity	On-site fossil fuel consumption due to project activity Combustion of waste gas for	CO ₂	Excluded	Project activity entails use of waste heat of the flue gases from DRI kilns for power generation. Project activity does not entail use of fossil fuels in the project activity. However, the minor emissions from on-site diesel consumption are negligible and are included. This is conservative and will be monitored at verification
	electricity generation	CH ₄	Excluded	Excluded for simplification. This is conservative.
		N ₂ O	Excluded	Excluded for simplification. This is conservative.





From the above boundary diagram, the steam source from the AFBC boiler has not been considered within the boundary as the steam from this source will be apportioned in line with the methodology so that the CoUs are claimed only for the electricity produced from the steam generated by the waste heat recovery boilers. The monitoring of the project activity will ensure that this is implemented in line with the monitoring methodology. The back-up diesel generators only have the capacity to rotate the kiln. The system is not designed to operate the sponge iron plant.

PEy = Project emissions in year y (tCO_2/y)

The project emissions, if any, due to the usage of fossil fuel (diesel) are calculated as follows:

 $PE_v = Q_i \cdot CO_{EFi} \cdot NCV_i \cdot OXID$

Where:

 $PE_v = project emissions in year y, tCO_2e$

Q_i = mass of fossil fuel combusted, t

CO_{EFi} = emissions factor of fossil fuel combusted, tCO₂/TJ

NCV_i = net calorific value of fossil fuel combusted, TJ/t

OXID = oxidation factor, %

PE_v = 91.62 tCO₂ over the monitored period



Year	2015	2016	2017	2018	2019	2020	2021	2022	Total
PE _y tCO ₂	5.43	2.17	1.67	7.13	44.22	20.33	8.65	2.02	91.62

Net GHG Emission Reductions and Removals

Thus, $ERy = BE_v - PE_v - LE_v$

Where:

 $ER_y = Emission reductions in year y (tCO_2/y)$

 BE_y = Baseline Emissions in year y (t CO_2/y)

 $LE_v = Leakage emissions in year y (tCO₂/y)$

Establishment and description of baseline scenario (Adapted CDM Methodology using UCR Protocol)

Baseline emissions include only CO₂ emissions from electricity generation in power plants that are displaced due to the project activity. The case established for the power required by the project activity, since it requires 1.8 MWh for its auxiliary use, is less than the installed capacity of the equipment as per the methodology and its associated emissions quantification formula to be selected.

The baseline emissions corresponding to electricity supplied by the project activity to recipient facilities is estimated for each recipient facility in accordance with the case established as above and in the case of the project activity is as follows:

(a) Case 1a: recipients whose project level electricity consumption is less than or up to the maximum capacity of the existing pre-project equipment at the recipient facility to use the following modified equation:



$$BE_{EL,j,y} = \sum_{i} (EG_{i,j,y} \times EF_{Elec,i,j,y})$$
 Equation (4)

Where:

 $EG_{i,j,y}$

The power supplied by the project activity to the recipient facility j, which in the absence of the project activity would have been sourced from baseline source i (e.g. 'gr' for the grid or 'is' for an identified source) during the year y as per the identified baseline scenario for recipient facility j (MWh)

 $EF_{Elec,i,j,y}$

The CO_2 emission factor for the baseline electricity source i (e.g. 'gr' for the grid, and 'is' for an identified source), corresponding to baseline scenario for the recipient facility j, during the year y (t CO_2/MWh)

f_{WCM} = Fraction of total electricity generated by the project activity using waste gas.

$$f_{WCM} = \frac{ST_{whr,y}}{ST_{whr,y} + ST_{other,y}}$$

Where:

ST_{whr,y} = Energy content of the steam generated in waste heat recovery boiler fed to turbine via common steam header

ST_{other,y} = Energy content of steam generated in other boiler (AFBC) fed to turbine via common steam header

(b) If the electricity displaced by the project activity in the recipient facility is supplied by a connected grid system, the CO₂ emission factor of the electricity is modified from the UNFCCC CDM methodology and instead shall be determined following the guidance provided by the UCR CoU protocol for conservativeness.

Power Gen Cap Capacity	MW	18
Auxiliary Power Consumption	%	10%

Annual Baseline Emission Reductions: BE $EL, j,y = f_{WCM}$ (EG $BL,y \times EF$, CO2, GRID, y)

BE $_{EL, j, y}$ = Baseline emission reductions in a year y at project site/recipient plant (j).

where:

 $EG_{BL,y}$ is calculated based on daily gross power generation and auxiliary power consumption in



the power generation plant (recipient plant)

EG
$$_{BL,y}$$
 = EG $_{GEN,y}$ — EG $_{AUX,y}$.

where:

EG BL,y = Net power generation from turbine in year y (MWh/yr)

EG GEN,y= Gross power generation from turbine in year y (MWh/yr)

EG AUX,y= Auxiliary power consumption in power generation plant in year y (MWh/yr)

 $EF_{Grid,CO2,y} = CO_2$ emission factor of the grid in year y (t CO_2/MWh) as determined by the UCR Standard for the 2015-2022 period.

A "grid emission factor" refers to a CO₂ emission factor (tCO₂/MWh) which will be associated with each unit of electricity provided by an electricity system.

The UCR recommends an emission factor of 0.9 tCO₂/MWh for the 2015-2021 years as a fairly conservative estimate for Indian projects not previously verified under any GHG program.

Also, for the vintage 2021-22, the combined margin emission factor calculated from CEA database in India results into same emission factors as that of the default value. Hence, the same emission factor has been considered to calculate the emission reduction.

No leakage is applicable under this methodology, hence, LE_y= 0

Year	Net electricity supplied	Total electricity generated	Auxiliary electricity	Net electricity supplied
	KWh	MWh	MWh	MWh
	EGy	EG _{Gen}	EG _{Aux}	EGy
2015	3,89,88,471	42,802	3,813	38,988.471
2016	12,22,44,093	1,33,534	11,290	1,22,244.093
2017	12,02,59,901	1,31,597	11,337	1,20,259.901
2018	12,34,78,170	1,33,931	10,453	1,23,478.170
2019	11,69,46,409	1,26,955	10,008	1,16,946.409
2020	11,25,71,870	1,20,934	8,379	1,12,571.870
2021	12,69,42,731	1,36,374	9,431	1,26,942.731
2022	12,91,46,264	1,38,242	9,096	1,29,146.264
Grand Total	89,05,77,909	9,64,368	73,807	8,90,577.91



Steam From Wilson Fisher Steam From Wilson Fisher Steam From Net			ST _{whr}			ST _{whr}			ST _{other}					*
				boiler #1			R boiler #2	Stean		bc boiler	oing to new 8	MW turbin	e from AFB	Quantity of
		emperatur	Pressure	Quantity	emperatur	ressure	Quantity	emperatu	Pressure	Quantity	Т	emperatu	Pressure	
					•	-		•	_					
Sep-16 492 84 65.38 15590.26 493.95 65.94 15432.90 496.16 65.26 1500.05.80 0.00 0.00 0.00 10500.05 (0.15) 494.08 65.53 13461.10 491.74 66.21 1911.185 5 500.55 65.22 24518.27 1306.27 1293.67 493.34 64.00 14146.3 190.00 150.00 1		Temp _{whr}	Press _{whr}	Quantity _{whr}	Temp _{whr}	Press _{whr}	Quantity _{whr}	Temp _{other}	Pressother	Quantity _{other}	Quantity _{8MW}	Temp _{8MW}		Quantity _{csh}
Nov-15 494.08 66.55 13451.10 491.74 66.21 19111.85 502.14 66.42 35604.28 2147.94 493.34 64.05 14163.84	Sep-15	492.84		15530.25	493.95		15432.90							10500.58
Dec-15 493.64 66.39 5039.00 498.19 66.01 18821.95 494.23 68.86 39682.02 2046.06 495.28 64.75 19034.85 491.16 494.16 66.55 17776.86 497.46 66.53 1775.20 5031.46 68.43 39687.22 23667.13 496.18 64.47 16932.75 Feb-16 494.25 66.95 17776.86 497.66 66.93 21790.85 510.36 68.73 37678.24 22745.53 496.18 64.47 16932.75 Feb-16 495.23 66.01 18050.35 493.41 66.49 17338.30 505.41 64.91 36159.50 23574.22 497.22 538.87 12588.55 Feb-17 496.20 66.60 19167.67 493.00 66.86 19168.86 66.20 527.04 69.91 69.91 Feb-16 496.20 66.60 19167.67 493.00 66.86 19145.85 500.59 68.77 35964.94 2220.12 491.35 64.40 12448.65 Feb-17 494.20 66.10 18102.85 64.70 66.30 18189.85 65.62 499.86 67.80 494.20 66.70 18189.85 65.62 499.86 66.80 494.20 66.70 18189.85 65.62 65.62 499.86 66.80 64.88 494.15 69.80 64.88 69.80 66.88 69.80 66.88 69.80 66.88 69.80 66.88 69.80 66.88 69.80 66	Oct-15	493.83			493.39	65.91	19093.55			24518.27	13905.27	492.23	64.20	10613.00
Jan-16 495.16 65.34 17768.05 493.23 65.99 1975.20 593.14 65.43 39657.22 22867.13 495.15 64.17 15990.05 1 Mar-16 483.65 65.07 15232.40 492.50 66.39 21970.85 510.36 65.13 37678.20 22475.24 501.18 64.47 16932.77 Mar-16 483.65 65.07 15232.40 492.50 66.39 21970.85 510.36 65.73 35843.74 22475.24 501.18 64.40 12885.25 May-16 494.91 65.66 1910.10 15.07 493.09 65.85 1980.07 64.91 36159.50 23674.24 1497.32 63.87 12885.25 May-16 494.91 65.66 1910.10 15.07 493.09 65.85 1980.07 64.90 20 65.38 29125.82 19915.37 489.69 64.40 12444.85 Jul-16 492.91 65.66 1910.10 15.07 493.09 65.85 1980.07 64.90 20 65.37 35684.49 22220.17 489.69 64.40 12444.85 Jul-16 493.55 65.88 16727.46 494.29 65.71 16884.75 496.17 65.93 35170.76 20172.73 486.66 64.80 1498.00 64.40 12444.85 Jul-16 493.00 64.00 8820.37 487.40 65.10 11819.35 501.63 65.4 39867.77 22785.19 493.37 64.85 15881.85 Sep-16 493.00 64.00 8820.37 487.40 65.10 11819.35 501.63 65.2 3940.48 30 18888.85 491.15 63.88 15816.07 Cet-16 492.00 66.10 11626.65 493.40 65.00 18894.00 65.63 498.00 65.63 498.00 65.00 12448.20 May-16 494.50 66.10 12448.20 493.20 66.00 18894.00 65.63 498.00 65.03 498.00 65.00 18894.00 65.00 1890.00 65.00 177345.50 494.50 65.00 18894.30 500.57 65.62 38992.88 22455.78 497.36 64.41 153537.15 Dec-16 495.00 64.90 14197.07 490.00 65.00 19740.75 68.00 1597.85 65.2 3900.075 2014.14 499.00 64.00 1497.00 65.00 15772.90 65.00 19740.75 68.00 1497.00 65.00 15772.90 65.00 19740.75 68.00 1497.00 65.00 15772.90 65.00 19740.75 68.00 1497.00 65.00 15772.90 65.00 19740.75 68.00 1497.00 65.00 15772.90 65.00 19740.75 68.00 1497.00 65.00 15772.90 65.00 1497.00 65.00 1497.00 65.00 1497.00 65.00 15772.90 65.00 1497.00 65.00 1497.						1							1	14146.34
Feb-16 494,25 68,96 17715,80 493,33 68,79 3032,35 504,83 66,51 37678,24 20745,55 496,18 64,47 16932,77 184,48 184,														
Name-16						1							1	
													-	
Jun-16 402.81 65.66 19015.75 493.09 65.85 19145.85 500.59 65.71 35664.40 21220.12 491.35 64.40 12444.82 11.16 403.55 65.88 16027.55 487.84 64.99 65.71 65.93 38170.76 201.73 486.96 64.88 14980.05 65.81 493.80 64.80 8629.70 487.40 65.10 11819.35 501.63 65.26 3404.83 1898.83 491.15 63.88 1516.00 61.00 61.00 1180.65 69.00 65.10 11819.35 501.63 65.26 3404.83 1898.83 491.15 63.88 1516.00 61.00 61.00 1180.65 69.30 180.24 65.90 180.00 65.63 14131.36 1898.83 491.15 63.88 1516.00 61.00														12585.28
	May-16	494.89	66.26	21345.60	492.13	65.96	19590.75	499.02	65.38	29125.82	19915.37	489.69	64.38	9210.45
Number 6491.23 65.36 16027.55 487.88 65.33 453.80 499.96 65.64 39646.77 23785.19 489.37 64.88 15861.58														12444.82
Sep-16 493.80 64.80 8629.70 497.40 65.10 11819.35 5016.3 65.28 34404.83 18988.83 491.15 63.88 15416.00	Jul-16	493.55	65.88	16727.45	494.29	65.71			65.93	35170.76			64.68	14998.03
Oct-16 492.00 66.10 11626.65 493.40 65.80 18464.05 498.00 65.63 41313.69 23928.55 487.34 64.42 17385.14	Aug-16	491.23	65.36	16027.55	487.88	65.33	4553.80	499.96	65.64	39646.77	23785.19	489.37	64.58	15861.58
Nov-16		493.80	64.80	8629.70	487.40	65.10	11819.35	501.63		34404.83	18988.83	491.15	63.88	15416.00
Dec-16 495.60 66.10 12448.20 493.20 66.40 20293.05 511.83 65.14 39834.83 22686.95 499.04 64.21 17147.88		492.00			493.40	65.80	18464.05				23928.55	487.34	64.42	17385.14
	Nov-16													15537.15
Feb-17 488.40 64.90 9748.75 488.90 65.20 9384.20 509.93 65.54 39000.75 20414.14 499.06 64.19 18586.61 Mar-17 494.70 66.10 13038.15 491.30 65.90 17197.65 511.23 65.89 40009.78 23266.61 501.02 64.73 16743.17 494.00 65.90 15728.90 491.10 65.00 4475.05 495.80 65.50 21476.05 495.80 65.50 21476.05 495.80 65.50 21476.05 495.80 65.50 21476.05 495.80 65.50 21476.05 495.80 65.50 21476.05 495.80 65.50 21476.05 495.80 65.50 21476.05 495.80 65.50 21476.05 495.80 65.70 18845.75 491.30 65.00 65.00 65.00 6805.10 490.10 65.10 15492.40 495.45 65.32 43527.89 20973.30 484.85 64.05 22584.55 499.71 496.00 64.90 14181.85 490.00 65.00 5586.50 501.49 65.59 43572.67 21082.59 490.56 64.19 22490.00 65.00 65.00 65.00 5586.50 501.49 65.59 43572.67 21082.59 490.56 64.19 22490.00 65.00 65.00 65.00 5866.50 501.49 65.59 43572.67 21082.59 490.56 64.19 22490.00 65.00 65.00 65.00 5866.50 501.49 65.59 43572.67 21082.59 490.56 64.19 22490.00 65.00 65.00 65.00 65.00 5866.50 501.49 65.59 43572.67 21082.59 490.56 64.19 22490.00 65.00	Dec-16	495.60	66.10	12448.20	493.20	66.40	20293.05			39834.83		499.04	64.21	17147.88
Main-17		494.50	64.90		490.20	65.60								15927.81
Apr-17	Feb-17	488.40	64.90	9748.75	488.90	65.20	9384.20	509.93	65.54	39000.75	20414.14	499.06	64.19	18586.61
May-17 496.50 66.10 15978.25 493.40 65.90 15778.40 499.62 65.87 40898.80 23209.51 490.13 64.74 17689.25	Mar-17	494.70	66.10	13038.15	491.30	65.90	17197.65	511.23	1	40009.78	23266.61	501.02	64.73	16743.17
Jun-17 494.80 65.70 16845.75 491.30 65.00 13139.00 500.48 65.94 40929.67 22659.30 488.37 64.66 18270.37 Jul-17 493.60 65.00 6805.10 490.10 65.10 15492.40 495.45 65.32 43527.89 20973.30 484.85 64.05 22564.55 Aug-17 496.00 64.90 14181.85 490.00 65.00 5968.50 501.49 65.59 43572.67 21082.59 490.56 64.19 22490.05 Sep-17 497.80 65.70 10829.20 489.10 65.40 15933.10 497.14 65.68 41117.24 22179.31 486.84 64.38 18937.93 Oct-17 496.20 65.60 15310.80 493.80 65.40 16212.70 496.06 65.68 40550.87 22215.07 483.97 64.46 18335.81 Nov-17 498.90 65.80 13470.10 493.70 65.60 16126.80 497.69 65.67 42088.8 22747.10 486.02 64.54 19331.75 Dec-17 492.00 66.40 11058.40 495.90 66.00 18087.15 496.94 65.61 39137.16 21862.68 484.05 64.47 17274.45 Jan-18 497.60 66.10 14884.15 467.00 65.60 19723.00 501.08 65.48 38549.63 23202.66 489.65 64.47 17274.94 Nov-18 498.80 66.30 17735.65 494.40 66.40 18576.05 502.04 65.57 40392.56 23896.13 488.95 64.55 18496.43 Apr-18 498.80 65.70 14663.30 494.50 66.30 19724.20 495.89 65.63 38438.94 22366.88 483.90 64.37 12977.95 Mar-18 499.30 66.20 18974.80 487.90 65.50 20955.35 495.25 65.13 35179.49 23624.73 484.23 64.12 11554.76 Jul-18 486.80 65.00 18215.75 493.90 66.90 18729.20 495.89 65.61 38714.94 23624.73 484.23 64.12 11554.76 Jul-18 486.80 65.00 18274.57 498.90 65.60 18729.20 495.55 65.79 34581.52 23062.16 482.59 64.43 1159.34 Jul-18 486.80 65.00 18274.57 498.90 65.60 18739.35 499.37 65.81 38716.50 23099.68 487.64 64.65 15706.62 Jul-18 499.90 65.00 18974.80 65.60 18739.35 499.37 65.38 4339.94 23268.88 483.90 64.43 1159.34 Dun-18 499.90 65.00 18091.75 498.50 65.60 18739.35 499.37 65.38 4309.94 23644.73 484.23 64.12 11554.76 Dec-18 499.90 65.00 13328.95 490.50 65.60 18739.35 499.37 65.38 4339.94 2364.81 1071.97 486.50 64.49 11727.17 Dec-18 499.90 65.00 13038.80 491.80 65.20 17593.30 499.93 65.81 43394.82 12088.70 486.50 64.49 11727.17 Dec-18 499.90 65.00 13038.80 491.80 65.00 13038.70 499.50 65.68 43041.24 23314.07 486.50 64.49 11727.17 Dec-18 499.90 66.00 10035.20 498.50 65.60 13739.35 499.37 65.38 4309.84 23344.	Apr-17	490.10	65.90	15729.90	491.10	65.00	14716.05	495.83	65.50	21406.03	12131.01	485.71	64.23	9275.02
Jul-17 493.60 65.00 6805.10 490.10 65.10 15492.40 495.45 65.32 43527.89 20973.30 484.85 64.05 22554.55 Aug-17 496.00 64.90 14181.85 490.00 65.00 5968.50 501.49 65.59 43572.67 21082.59 490.56 64.19 22490.00 Sep-17 497.80 65.70 10829.20 489.10 65.40 15933.10 497.14 65.68 41117.24 22179.31 486.84 64.38 18937.93 Cet-17 496.20 65.60 15310.80 493.80 65.40 16212.70 496.06 65.68 40550.87 22215.07 489.97 64.46 18335.80 Nov-17 498.90 65.80 13470.10 493.70 65.60 16126.80 497.69 65.67 42088.88 22747.10 486.02 64.54 19341.76 Dec-17 492.00 66.40 11058.40 495.90 66.00 18087.15 496.94 65.61 39137.16 21862.68 484.05 64.47 17274.45 Jan-18 497.60 66.10 14884.15 467.00 65.60 19723.00 501.08 65.48 38549.63 23202.65 489.65 64.47 15346.95 Feb-18 496.80 66.30 17735.65 494.40 66.40 9946.40 502.84 65.57 34238.28 21260.33 489.90 64.37 12977.95 Mar-18 496.70 66.20 15166.85 494.40 66.40 18576.05 502.04 65.57 40392.56 23896.13 488.95 64.55 16466.30 497.40 492.90 66.30 19724.20 495.89 65.63 33438.94 22368.88 483.90 64.45 1670.00 May-18 499.30 66.20 18974.80 487.90 65.50 20955.35 495.25 65.13 35179.49 23624.73 484.23 64.12 11554.76 Jul-18 486.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.73 34581.52 23062.16 482.59 64.40 1870.00 18729.20 495.55 65.73 34581.52 23062.16 482.59 64.40 1870.00 18729.20 495.55 65.73 34581.52 23062.16 482.59 64.40 1870.00 18729.20 495.55 65.73 34581.52 23062.16 482.59 64.41 11554.76 Sep-18 499.90 65.00 10901.75 498.50 65.60 18729.20 495.55 65.73 34581.52 23062.16 482.59 64.43 11519.36 Dec-18 499.90 65.00 10901.75 498.50 65.60 18709.30 499.50 65.60 40041.44 23314.07 48	May-17	496.50	66.10	15978.25	493.40	65.90	15778.40	499.62	65.87	40898.80	23209.51	490.13	64.74	17689.29
Aug-17 496.00 64.90 14181.85 490.00 65.00 5968.50 501.49 66.59 43572.67 21082.59 490.56 64.19 22490.00	Jun-17	494.80	65.70	16845.75	491.30	65.00	13139.00	500.48	65.94	40929.67	22659.30	489.37	64.66	18270.37
Sep-17 497.80 65.70 10829.20 489.10 65.40 15933.10 497.14 65.68 41117.24 22179.31 486.84 64.38 18937.93 Oct-17 496.20 65.60 15310.80 493.80 65.60 16212.70 496.06 65.88 40550.87 22215.07 483.97 64.46 18335.81 Nov-17 498.90 65.80 13470.10 493.70 65.60 16126.80 497.69 66.67 42088.88 22747.10 486.02 64.54 19341.78 Dec-17 492.00 66.40 11058.40 495.90 66.00 18087.15 496.94 65.61 39137.16 21862.68 484.05 64.47 15346.98 Jan-18 497.60 66.10 14884.15 467.00 65.60 19723.00 501.08 65.48 38549.63 23202.65 498.65 64.47 15346.98 Feb-18 496.80 66.20 15166.85 494.40 66.40 9946.40 502.84 65.57 40	Jul-17	493.60	65.00	6805.10	490.10	65.10	15492.40	495.45	65.32	43527.89	20973.30	484.85	64.05	22554.59
Oct-17 496.20 65.60 15310.80 493.80 65.40 16212.70 496.06 65.68 40550.87 22215.07 483.97 64.46 18335.80 Nov-17 498.90 65.80 13470.10 493.70 65.60 16126.80 497.69 65.67 42088.88 22747.10 486.02 64.54 19341.76 Dec-17 492.00 66.40 11058.40 495.90 66.00 18087.15 496.94 65.61 39137.16 21862.68 484.05 64.47 17274.48 Jan-18 497.60 66.10 14884.15 467.00 65.60 19723.00 501.08 65.48 38549.63 23202.65 489.65 64.47 15346.95 Feb-18 496.80 66.30 17735.65 494.40 66.40 19576.05 502.04 65.57 40392.56 23896.13 488.95 64.57 12977.95 Mar-18 496.70 66.20 15166.85 494.40 66.40 18576.05 502.04 65.57 4	Aug-17	496.00	64.90	14181.85	490.00	65.00	5968.50	501.49	65.59	43572.67	21082.59	490.56	64.19	22490.08
Nov-17 498.90 65.80 13470.10 493.70 65.60 16126.80 497.69 65.67 42088.88 22747.10 486.02 64.54 19341.76 Dec-17 492.00 66.40 11058.40 495.90 66.00 18087.15 496.94 65.61 39137.16 21862.68 484.05 64.47 17274.48 Jan-18 497.60 66.10 14884.15 467.00 65.60 19723.00 501.08 65.48 38549.63 23202.65 489.65 64.47 15346.98 Feb-18 496.80 66.30 17735.65 494.40 65.40 9946.40 502.84 65.37 34238.28 21260.33 489.00 64.37 12977.98 Mar-18 496.70 66.20 15166.85 494.40 66.40 18576.05 502.04 65.57 40392.56 23896.13 488.95 64.55 16496.43 Apr-18 498.80 65.70 14663.30 494.50 66.30 19724.20 495.89 65.63 38438.94 22368.88 483.90 64.48 16070.06 May-18 499.30 66.20 18974.80 487.90 65.50 20955.35 495.25 66.13 35179.49 2362.473 484.23 64.12 11554.75 Jun-18 482.10 65.60 15215.75 493.90 65.90 18931.95 499.34 65.81 38716.50 23009.68 487.64 64.56 15706.83 Jul-18 498.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.79 34581.52 23062.16 482.59 64.49 11573.84 Aug-18 497.10 65.30 10901.75 498.50 65.60 18739.35 499.09 65.86 40341.24 23314.07 486.56 64.49 19727.10 Sep-18 493.60 65.20 13328.95 490.50 65.80 8606.15 499.61 65.49 40896.91 21013.97 485.43 64.22 19882.94 Oct-18 499.90 65.10 10891.80 491.80 65.20 13707.35 499.37 65.38 44359.48 21088.70 486.94 64.07 23270.76 Dec-18 499.90 65.10 10891.80 491.80 65.20 13707.35 499.37 65.38 44359.48 21088.70 486.94 64.07 23270.76 Dec-18 499.90 65.00 15296.55 498.70 65.00 10316.70 499.61 65.64 30486.48 16181.25 486.62 64.38 14705.25 Feb-19 498.60 65.20 13056.51 499.00 65.80 10316.70 499.61 65.64 34464.73 18548.17 487.33 64.41 15916.56 Dec-18 499.90 65.60 11596.20 499.00 65.60 116059.05 499.90 65.66 39804.44 22595.38 486.25 64.17 17209.06 Dec-18 499.90 65.00 15366.15 499.00 65.00 10316.70 499.61 65.64 34464.73 18548.17 487.33 64.41 15916.56 Dec-18 499.10 65.20 11094.70 496.40 65.20 17593.30 499.90 65.66 39804.44 22595.38 486.25 64.17 17209.06 Dec-18 499.90 65.60 15266.60 16059.05 499.90 65.60 39804.44 22595.38 486.25 64.17 17209.06 Dec-19 494.00 65.20 11586.20 489.00 65.00 16059	Sep-17	497.80	65.70	10829.20	489.10	65.40	15933.10	497.14	65.68	41117.24	22179.31	486.84	64.38	18937.93
Dec-17	Oct-17	496.20	65.60	15310.80	493.80	65.40	16212.70	496.06	65.68	40550.87	22215.07	483.97	64.46	18335.80
Jan-18	Nov-17	498.90	65.80	13470.10	493.70	65.60	16126.80	497.69	65.67	42088.88	22747.10	486.02	64.54	19341.78
Feb-18 496.80 66.30 17735.65 494.40 65.40 9946.40 502.84 65.37 34238.28 21260.33 489.00 64.37 12977.95 Mar-18 496.70 66.20 15166.85 494.40 66.40 18576.05 502.04 65.57 40392.56 23896.13 488.95 64.55 16496.43 Apr-18 498.80 65.70 14663.30 494.50 66.30 19724.20 495.89 65.63 38438.94 223624.73 484.23 64.12 11554.76 Jun-18 499.30 66.20 18974.80 487.90 65.50 20955.35 495.25 65.13 35179.49 23624.73 484.23 64.12 11554.76 Jun-18 482.10 65.60 15215.75 493.90 65.80 18729.20 495.55 65.79 34581.52 23006.64 482.99 64.43 11519.34 Jul-18 486.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.79 34	Dec-17	492.00	66.40	11058.40	495.90	66.00	18087.15	496.94	65.61	39137.16	21862.68	484.05	64.47	17274.48
Feb-18 496.80 66.30 17735.65 494.40 65.40 9946.40 502.84 65.37 34238.28 21260.33 489.00 64.37 12977.95 Mar-18 496.70 66.20 15166.85 494.40 66.40 18576.05 502.04 65.57 40392.56 23896.13 488.95 64.55 16496.43 Apr-18 498.80 65.70 14663.30 494.50 66.30 19724.20 495.89 65.63 38438.94 223624.73 484.23 64.12 11554.76 Jun-18 499.30 66.20 18974.80 487.90 65.50 20955.35 495.25 65.13 35179.49 23624.73 484.23 64.12 11554.76 Jun-18 482.10 65.60 15215.75 493.90 65.80 18729.20 495.55 65.79 34581.52 23006.64 482.99 64.43 11519.34 Jul-18 486.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.79 34														
Mar-18 496.70 66.20 15166.85 494.40 66.40 18576.05 502.04 65.57 40392.56 23896.13 488.95 64.55 16496.43 Apr-18 498.80 65.70 14663.30 494.50 66.30 19724.20 495.89 65.63 38438.94 22368.88 483.90 64.48 16070.06 May-18 499.30 66.20 18974.80 487.90 65.50 20955.35 495.25 65.13 35179.49 23624.73 484.23 64.12 11554.76 Jul-18 482.10 65.60 15215.75 493.90 65.80 18729.20 495.55 65.79 34581.52 23096.16 482.59 64.43 11519.36 Aug-18 496.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.79 34581.52 23062.16 482.59 64.43 11519.36 Aug-18 497.10 65.20 13328.95 490.50 65.80 9606.15 499.99 65.86 430	Jan-18	497.60	66.10	14884.15	467.00	65.60	19723.00	501.08	65.48	38549.63	23202.65	489.65	64.47	15346.98
Apr-18 498.80 65.70 14663.30 494.50 66.30 19724.20 495.89 65.63 38438.94 22368.88 483.90 64.48 16070.06 May-18 499.30 66.20 18974.80 487.90 65.50 20955.35 495.25 65.13 35179.49 23624.73 484.23 64.12 11554.76 Jun-18 482.10 65.60 15215.75 493.90 65.90 18931.95 499.34 65.81 38716.50 23009.68 487.64 64.56 15706.82 Jul-18 486.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.79 34581.52 23062.16 482.59 64.43 11519.36 Aug-18 497.10 65.30 10901.75 498.50 65.60 18739.35 499.01 65.40 43041.24 23314.07 486.56 64.49 19727.17 Sep-18 493.60 65.20 13328.95 490.50 65.80 9606.15 499.61 65.49 210	Feb-18	496.80	66.30	17735.65	494.40	65.40	9946.40	502.84	65.37	34238.28	21260.33	489.00	64.37	12977.95
May-18 499.30 66.20 18974.80 487.90 65.50 20955.35 495.25 65.13 35179.49 23624.73 484.23 64.12 11554.76 Jun-18 482.10 65.60 15215.75 493.90 65.90 18931.95 499.34 65.81 38716.50 23009.68 487.64 64.56 15706.82 Jul-18 486.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.79 34581.52 23062.16 482.59 64.43 11519.36 Aug-18 497.10 65.30 10901.75 498.50 65.60 18739.35 499.09 65.86 43041.24 23314.07 486.56 64.49 19727.17 Sep-18 493.60 65.20 13328.95 490.50 65.80 9606.15 499.61 65.49 40896.91 21013.97 485.43 64.22 19882.94 Oct-18 499.90 65.10 10891.80 491.80 65.20 13707.35 499.37 65.38 443	Mar-18	496.70	66.20	15166.85	494.40	66.40	18576.05	502.04	65.57	40392.56	23896.13	488.95	64.55	16496.43
Jun-18 482.10 65.60 15215.75 493.90 65.90 18931.95 499.34 65.81 38716.50 23009.68 487.64 64.56 15706.82 Jul-18 486.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.79 34581.52 23062.16 482.59 64.43 11519.36 Aug-18 497.10 65.30 10901.75 498.50 65.60 18739.35 499.09 65.86 43041.24 23314.07 486.56 64.49 19727.17 Sep-18 493.60 65.20 13328.95 490.50 65.80 9606.15 499.61 65.49 40896.91 21013.97 485.43 64.22 19882.94 Oct-18 499.90 65.10 10891.80 491.80 65.20 13707.35 499.37 65.38 44359.48 21088.70 486.94 64.07 23270.76 Nor-18 494.90 66.10 12797.05 498.30 65.40 15941.25 498.65 65.58 400	Apr-18	498.80	65.70	14663.30	494.50	66.30	19724.20	495.89	65.63	38438.94	22368.88	483.90	64.48	16070.06
Jul-18 486.80 65.40 6492.10 492.90 65.80 18729.20 495.55 65.79 34581.52 23062.16 482.59 64.43 11519.36 Aug-18 497.10 65.30 10901.75 498.50 65.60 18739.35 499.09 65.86 43041.24 23314.07 486.56 64.49 19727.17 Sep-18 493.60 65.20 13328.95 490.50 65.80 9606.15 499.61 65.49 40896.91 21013.97 485.43 64.22 19882.94 Oct-18 499.90 65.10 10891.80 491.80 65.20 13707.35 499.37 65.38 44359.48 21088.70 486.94 64.07 23270.76 Nov-18 494.90 66.10 12797.05 498.30 65.40 15941.25 498.65 65.58 40013.33 21651.57 486.51 64.39 18361.76 Dec-18 499.10 65.20 11094.70 496.40 65.20 17593.30 499.53 65.73 418														11554.76
Aug-18 497.10 65.30 10901.75 498.50 65.60 18739.35 499.09 65.86 43041.24 23314.07 486.56 64.49 19727.17 Sep-18 493.60 65.20 13328.95 490.50 65.80 9606.15 499.61 65.49 40896.91 21013.97 485.43 64.22 19882.94 Oct-18 499.90 65.10 10891.80 491.80 65.20 13707.35 499.37 65.38 44359.48 21088.70 486.94 64.07 23270.76 Nov-18 494.90 66.10 12797.05 498.30 65.40 15941.25 498.65 65.58 40013.33 21651.57 486.51 64.39 18361.76 Dec-18 499.10 65.20 11094.70 496.40 65.20 17593.30 499.53 65.73 41850.08 22321.23 487.22 64.53 19528.85 Jan-19 495.10 65.70 10935.20 493.00 66.10 19224.45 499.03 65.44 30														15706.82
Sep-18 493.60 65.20 13328.95 490.50 65.80 9606.15 499.61 65.49 40896.91 21013.97 485.43 64.22 19882.94 Oct-18 499.90 65.10 10891.80 491.80 65.20 13707.35 499.37 65.38 44359.48 21088.70 486.94 64.07 23270.78 Nov-18 494.90 66.10 12797.05 498.30 65.40 15941.25 498.65 65.58 40013.33 21651.57 486.51 64.39 18361.76 Dec-18 499.10 65.20 11094.70 496.40 65.20 17593.30 499.53 65.73 41850.08 22321.23 487.22 64.53 19528.85 Jan-19 495.10 65.70 10935.20 493.00 66.10 19224.45 499.03 65.44 30886.48 16181.25 486.62 64.38 14705.25 Feb-19 498.60 65.20 10295.55 498.70 65.00 10316.70 499.61 65.64 34														11519.36
Oct-18 499.90 65.10 10891.80 491.80 65.20 13707.35 499.37 65.38 44359.48 21088.70 486.94 64.07 23270.76 Nov-18 494.90 66.10 12797.05 498.30 65.40 15941.25 498.65 65.58 40013.33 21651.57 486.51 64.39 18361.76 Dec-18 499.10 65.20 11094.70 496.40 65.20 17593.30 499.53 65.73 41850.08 22321.23 487.22 64.53 19528.85 Jan-19 495.10 65.70 10935.20 493.00 66.10 19224.45 499.03 65.44 30886.48 16181.25 486.62 64.38 14705.23 Feb-19 498.60 65.20 10295.55 498.70 65.00 10316.70 499.61 65.64 34464.73 18548.17 487.33 64.41 15916.55 Mar-19 494.90 65.20 15366.15 490.20 65.30 17236.75 498.99 65.56 3														
Nov-18 494.90 66.10 12797.05 498.30 65.40 15941.25 498.65 65.58 40013.33 21651.57 486.51 64.39 18361.76 Dec-18 499.10 65.20 11094.70 496.40 65.20 17593.30 499.53 65.73 41850.08 22321.23 487.22 64.53 19528.85 Jan-19 495.10 65.70 10935.20 493.00 66.10 19224.45 499.03 65.44 30886.48 16181.25 486.62 64.38 14705.23 Feb-19 498.60 65.20 10295.55 498.70 65.00 10316.70 499.61 65.64 34464.73 18548.17 487.33 64.41 15916.56 Mar-19 494.90 65.20 15366.15 490.20 65.30 17236.75 498.99 65.56 39804.44 22595.38 486.25 64.17 17209.06 Apr-19 500.30 66.20 12986.15 495.10 66.00 16059.05 495.71 65.78 37513.20 20210.73 484.34 64.71 17302.47 May-19 494.70 65.20 11958.20 490.10 65.60 17653.05 497.03 65.49 42374.77 22678.36 484.91 64.36 19696.41 Jun-19 490.10 65.80 10448.15 494.90 65.70 16725.90 496.14 65.74 36929.88 19385.97 484.29 64.52 17543.91 Jul-19 503.30 66.60 10752.65 469.20 65.60 15733.20 502.52 65.78 41868.83 21058.56 490.01 64.76 20810.27 Aug-19 504.30 66.00 2668.75 498.00 65.30 13349.50 498.26 65.91 37324.73 15579.05 493.92 64.54 21745.66 Oct-19 493.70 66.20 16565.15 497.90 65.30 12460.05 497.99 65.67 43545.47 22333.92 493.85 64.31 21211.55														19882.94
Dec-18 499.10 65.20 11094.70 496.40 65.20 17593.30 499.53 65.73 41850.08 22321.23 487.22 64.53 19528.88 Jan-19 495.10 65.70 10935.20 493.00 66.10 19224.45 499.03 65.44 30886.48 16181.25 486.62 64.38 14705.23 Feb-19 498.60 65.20 10295.55 498.70 65.00 10316.70 499.61 65.64 34464.73 18548.17 487.33 64.41 15916.56 Mar-19 494.90 65.20 15366.15 490.20 65.30 17236.75 498.99 65.56 39804.44 22595.38 486.25 64.17 17209.06 Apr-19 500.30 66.20 12986.15 495.10 66.00 16059.05 495.71 65.78 37513.20 20210.73 484.34 64.71 17209.06 Apr-19 490.70 65.20 11958.20 490.10 65.60 17653.05 497.03 65.49 4														23270.78
Jan-19 495.10 65.70 10935.20 493.00 66.10 19224.45 499.03 65.44 30886.48 16181.25 486.62 64.38 14705.23 Feb-19 498.60 65.20 10295.55 498.70 65.00 10316.70 499.61 65.64 34464.73 18548.17 487.33 64.41 15916.56 Mar-19 494.90 65.20 15366.15 490.20 65.30 17236.75 498.99 65.56 39804.44 22595.38 486.25 64.17 17209.06 Apr-19 500.30 66.20 12986.15 495.10 66.00 16059.05 495.71 65.78 37513.20 20210.73 484.34 64.71 17302.47 May-19 494.70 65.20 11958.20 490.10 65.60 17653.05 497.03 65.49 42374.77 22678.36 484.91 64.36 19696.41 Jun-19 490.10 65.80 10448.15 494.90 65.70 16725.90 496.14 65.74 3			 											18361.76
Feb-19 498.60 65.20 10295.55 498.70 65.00 10316.70 499.61 65.64 34464.73 18548.17 487.33 64.41 15916.66 Mar-19 494.90 65.20 15366.15 490.20 65.30 17236.75 498.99 65.56 39804.44 22595.38 486.25 64.17 17209.06 Apr-19 500.30 66.20 12986.15 495.10 66.00 16059.05 495.71 65.78 37513.20 20210.73 484.34 64.71 17302.47 May-19 494.70 65.20 11958.20 490.10 65.60 17653.05 497.03 65.49 42374.77 22678.36 484.91 64.36 19696.41 Jun-19 490.10 65.80 10448.15 494.90 65.70 16725.90 496.14 65.74 36929.88 19385.97 484.29 64.52 17543.91 Jul-19 503.30 66.60 10752.65 469.20 65.60 15733.20 502.52 65.78 4														
Mar-19 494.90 65.20 15366.15 490.20 65.30 17236.75 498.99 65.56 39804.44 22595.38 486.25 64.17 17209.06 Apr-19 500.30 66.20 12986.15 495.10 66.00 16059.05 495.71 65.78 37513.20 20210.73 484.34 64.71 17302.47 May-19 494.70 65.20 11958.20 490.10 65.60 17653.05 497.03 65.49 42374.77 22678.36 484.91 64.36 19696.41 Jun-19 490.10 65.80 10448.15 494.90 65.70 16725.90 496.14 65.74 36929.88 19385.97 484.29 64.52 17543.91 Jul-19 503.30 66.60 10752.65 469.20 65.60 15733.20 502.52 65.78 41868.83 21058.56 490.01 64.76 20810.27 Aug-19 506.10 65.30 11498.60 486.20 65.30 10754.90 499.02 65.42 2														
Apr-19 500.30 66.20 12986.15 495.10 66.00 16059.05 495.71 65.78 37513.20 20210.73 484.34 64.71 17302.47 May-19 494.70 65.20 11958.20 490.10 65.60 17653.05 497.03 65.49 42374.77 22678.36 484.91 64.36 19696.41 Jun-19 490.10 65.80 10448.15 494.90 65.70 16725.90 496.14 65.74 36929.88 19385.97 484.29 64.52 17543.91 Jul-19 503.30 66.60 10752.65 469.20 65.60 15733.20 502.52 65.78 41868.83 21058.56 490.01 64.76 20810.27 Aug-19 506.10 65.30 11498.60 486.20 65.30 10754.90 499.02 65.42 28826.17 13248.76 485.61 64.39 15577.41 Sep-19 504.30 66.00 2668.75 498.00 65.30 13349.50 498.26 65.91 37														
May-19 494.70 65.20 11958.20 490.10 65.60 17653.05 497.03 65.49 42374.77 22678.36 484.91 64.36 19696.41 Jun-19 490.10 65.80 10448.15 494.90 65.70 16725.90 496.14 65.74 36929.88 19385.97 484.29 64.52 17543.91 Jul-19 503.30 66.60 10752.65 469.20 65.60 15733.20 502.52 65.78 41868.83 21058.56 490.01 64.76 20810.27 Aug-19 506.10 65.30 11498.60 486.20 65.30 10754.90 499.02 65.42 28826.17 13248.76 485.61 64.39 15577.41 Sep-19 504.30 66.00 2668.75 498.00 65.30 13349.50 498.26 65.91 37324.73 15579.05 493.92 64.54 21745.68 Oct-19 493.70 66.20 16565.15 497.90 65.30 12460.05 497.99 65.67 43														
Jun-19 490.10 65.80 10448.15 494.90 65.70 16725.90 496.14 65.74 36929.88 19385.97 484.29 64.52 17543.91 Jul-19 503.30 66.60 10752.65 469.20 65.60 15733.20 502.52 65.78 41868.83 21058.56 490.01 64.76 20810.27 Aug-19 506.10 65.30 11498.60 486.20 65.30 10754.90 499.02 65.42 28826.17 13248.76 485.61 64.39 15577.41 Sep-19 504.30 66.00 2668.75 498.00 65.30 13349.50 498.26 65.91 37324.73 15579.05 493.92 64.54 21745.68 Oct-19 493.70 66.20 16565.15 497.90 65.30 12460.05 497.99 65.67 43545.47 22333.92 493.85 64.31 21211.55														
Jul-19 503.30 66.60 10752.65 469.20 65.60 15733.20 502.52 65.78 41868.83 21058.56 490.01 64.76 20810.27 Aug-19 506.10 65.30 11498.60 486.20 65.30 10754.90 499.02 65.42 28826.17 13248.76 485.61 64.39 15577.41 Sep-19 504.30 66.00 2668.75 498.00 65.30 13349.50 498.26 65.91 37324.73 15579.05 493.92 64.54 21745.68 Oct-19 493.70 66.20 16565.15 497.90 65.30 12460.05 497.99 65.67 43545.47 22333.92 493.85 64.31 21211.55	_													
Aug-19 506.10 65.30 11498.60 486.20 65.30 10754.90 499.02 65.42 28826.17 13248.76 485.61 64.39 15577.41 Sep-19 504.30 66.00 2668.75 498.00 65.30 13349.50 498.26 65.91 37324.73 15579.05 493.92 64.54 21745.68 Oct-19 493.70 66.20 16565.15 497.90 65.30 12460.05 497.99 65.67 43545.47 22333.92 493.85 64.31 21211.55														
Sep-19 504.30 66.00 2668.75 498.00 65.30 13349.50 498.26 65.91 37324.73 15579.05 493.92 64.54 21745.68 Oct-19 493.70 66.20 16565.15 497.90 65.30 12460.05 497.99 65.67 43545.47 22333.92 493.85 64.31 21211.55														
Oct-19 493.70 66.20 16565.15 497.90 65.30 12460.05 497.99 65.67 43545.47 22333.92 493.85 64.31 21211.55														
Dec-19 502.30 65.80 10878.20 496.80 65.10 11622.65 499.51 65.63 44538.84 19728.98 494.32 64.40 24809.86														24809.86



Jan-20	500.00	65.70	13330.95	493.80	65.00	13879.50	498.79	65.68	43621.63	21467.77	494.16	64.50	22153.86
Feb-20	500.50	65.40	11759.95	499.00	64.80	14102.75	499.33	65.81	40514.84	19945.69	494.71	64.56	20569.15
Mar-20	496.30	65.40	9747.00	499.90	65.20	10751.10	499.39	65.76	32555.25	15270.71	494.90	64.46	17284.54
Apr-20	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
May-20	500.00	65.40	11842.60	496.80	64.90	11282.65	499.51	65.71	43333.09	18845.83	494.41	64.42	24487.26
Jun-20	497.70	65.60	12739.75	494.80	64.60	11787.70	497.92	65.48	38789.68	17598.80	493.58	64.17	21190.88
Jul-20	496.30	65.70	12584.60	495.90	64.60	11091.70	498.07	65.61	40419.24	18405.51	493.34	64.29	22013.73
Aug-20	501.30	66.50	14781.20	487.20	64.90	10829.00	497.13	65.55	44119.34	19834.48	492.78	64.30	24284.86
Sep-20	498.50	66.80	18739.60	495.30	65.50	11876.10	495.25	65.67	38136.68	19227.21	490.27	64.72	18909.47
Oct-20	498.70	66.70	16454.40	497.70	65.00	12298.80	497.87	65.52	41085.65	19535.23	493.27	64.43	21550.42
Nov-20	491.20	66.50	15154.30	500.60	65.70	8201.90	495.88	65.53	39899.28	17577.60	492.32	64.53	22321.68
Dec-20	492.30	66.90	9504.60	498.70	65.40	13625.80	496.48	65.84	42540.77	19512.14	493.02	64.74	23028.63
Jan-21	502.20	66.50	15928.20	501.00	65.50	15135.20	497.90	65.68	40788.56	20376.78	493.75	64.52	20411.78
Feb-21	499.20	66.00	13648.30	497.90	65.50	14930.20	495.21	65.54	36462.13	19863.82	490.80	64.45	16598.31
Mar-21	496.00	66.70	15732.50	496.50	65.90	17348.60	496.81	65.62	39975.76	22374.93	491.74	64.65	17600.83
Apr-21	493.20	66.30	14405.40	494.00	65.40	14739.10	495.72	65.75	38828.18	19713.53	491.59	64.47	19114.65
May-21	499.30	66.40	8886.55	498.40	65.20	8455.80	495.88	65.64	25050.77	12235.75	491.60	64.47	12815.02
Jun-21	490.10	67.40	17056.80	495.50	65.80	16060.70	494.70	65.45	38485.37	22001.39	491.22	64.49	16483.98
Jul-21	498.50	67.80	19352.60	497.20	65.80	16928.40	494.89	65.80	39688.90	23992.05	490.88	64.54	15696.85
Aug-21	500.70	68.20	15091.00	497.50	66.00	17239.10	494.65	65.45	36663.42	20330.92	491.06	64.51	16332.50
Sep-21	498.80	67.20	18950.50	499.40	65.00	12248.60	494.88	65.74	39429.71	21682.58	491.38	64.36	17747.13
Oct-21	502.10	67.20	15943.00	498.10	65.20	14237.80	498.56	65.73	43823.11	22197.11	494.12	64.47	21626.00
Nov-21	498.10	67.20	14858.70	496.30	64.90	13444.30	497.95	65.60	42182.32	21077.05	493.72	64.38	21105.27
Dec-21	497.50	68.50	16551.60	497.60	65.80	14955.60	498.12	65.91	41854.86	22203.09	493.43	64.87	19651.77
Jan-22	500.50	68.40	19597.60	495.10	66.10	19488.40	492.32	65.78	37636.37	23898.62	489.80	64.77	13737.75
Feb-22	499.00	67.40	7351.20	491.10	65.30	17266.20	497.53	65.83	32625.70	15768.20	493.87	64.52	16857.50
Mar-22	501.30	66.70	16761.10	484.00	64.70	10980.90	497.07	65.54	42478.23	21826.67	492.97	64.24	20651.56
Apr-22	499.20	68.40	16122.50	496.00	66.80	17758.90	498.38	66.26	35990.91	21690.52	493.96	65.20	14300.39
May-22	497.50	67.50	18824.80	497.10	65.70	19850.20	496.52	65.79	38621.25	23605.51	493.41	64.52	15015.74
Jun-22	494.90	68.80	19053.50	494.80	66.60	19019.00	496.21	65.91	36909.81	22810.87	489.99	64.98	14098.94
Jul-22	497.30	68.78	20199.00	493.10	66.00	18906.20	496.24	65.73	21864.58	18060.36	492.55	64.68	3804.22
Aug-22	498.50	69.40	21247.70	495.80	66.00	17273.60	491.59	65.55	37609.53	23798.29	487.48	64.74	13811.24
Sep-22	486.20	68.10	8122.00	488.30	65.70	10058.40	496.65	65.71	41500.69	18099.20	492.44	64.44	23401.49
Oct-22	497.10	68.50	14168.60	497.20	65.50	16098.50	493.87	65.49	42863.46	22519.10	498.48	64.23	20344.36
Nov-22	499.30	68.60	15092.40	496.20	65.50	17961.20	494.62	65.91	40811.52	23136.11	491.30	64.68	17675.41
Dec-22	504.10	69.20	19121.90	464.00	65.90	18381.10	496.30	65.38	39796.62	23185.22	491.43	64.31	16611.40
Total	490.57	65.55	1226563.35	487.43	64.81	1330555.70	493.18	64.87	3312910.19	20425.11	479.79	5541.78	1515500.08

Issuance Period: 01/09/2015 to 31/12/2022

Year	BEy (tCO ₂)	PEy (tCO ₂)	ERy (tCO₂)
2015	24389.70	5.4315347	24382
2016	75200.60	2.1726139	75194
2017	65949.71	1.67	65941
2018	71604.94	7.1306301	71590
2019	61043.31	44.215478	60993
2020	54506.84	20.33	54482
2021	71716.85	8.6514599	71703
2022	78711.42	2.0166313	78704
Total	5,03,123.37	91.62	5,02,989



Total Emission Reductions for the current crediting period = 5,02,989 tCO₂eq (5,02,989 CoUs)

Conclusions:

Based on the audit conducted on the basis of UCR Protocol, which draws reference from UCR Protocol Standard Baseline, ACM0012 Waste energy recovery Version 6.0, the documents submitted during the verification including the Data, Project Concept Note (PCN) / Monitoring Report (MR), SQAC is able to certify that the emission reductions from the project - SBPIL Waste Heat to Power Project, Borjhara, India (UCR ID – 400) for the period **01/09/2015** to **31/12/2022** amounts to **5,02,989** COUS (5,02,989 tCO₂eq)

Sheetal Wader Lead Verifier (Signature) Oditication of the Control of the Co

Santosh Nair Senior Internal Reviewer (Signature)

Date: 12/03/2024